

## Analysis

**OD/359/3433/119016/416941/00072282 : Improvement of Rural Haat at Mundigada  
Block : Tumudibandh, Gram Panchayat : Mundigarh  
Created By: BANABIHARI HARAPAL**

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					1787.94
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					1922.0355
<b>LABOUR CESS @ 1% (+)</b>					275.491755
<b>Grand Total</b>					27824.667255
<b>Say For Unit 1 (Grand Total/100)</b>					278.24667255

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	70	7000	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0
<b>Total Amount (a+b+c)</b>				50846.32	
<b>Total GST (a)</b>				0	
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				3813.474	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				4099.48455	
<b>LABOUR CESS @ 1% (+)</b>				587.5927855	
<b>Grand Total</b>				59346.8713355	
<b>Say For Unit 1 (Grand Total/100)</b>				593.468713355	

### Item 3

**Concrete (AR0303a):** Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work  
**Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	578.12	1323.8948	238.301064
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	149.5	143.52	0

<b>Total Amount (a+b+c)</b>	4775.28548
-----------------------------	------------

<b>Total GST (a)</b>	238.301064
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	376.0189908
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	404.22041511
<b>LABOUR CESS @ 1% (+)</b>	57.9382594991
<b>Grand Total</b>	5851.7642094091
<b>Say For Unit 1 (Grand Total/1)</b>	5851.7642094091

#### Item 4

**Masonry Stone Work (AR0703):** Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Random rubble H.G. stone of masonry.**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.41	Per day	462	651.42	0
LR001 : Male mulia	1.76	Per day	462	813.12	0
LR025 : Mason	1.41	Per day	562	792.42	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.8151	1 Qntl.	578.12	471.225612	84.82061016
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	76.88	26.1392	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	291.96	291.96	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.8151	1 Qntl.	30.732	25.0496532	0
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	406.21	138.1114	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	406.21	406.21	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.8151	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	40.25	13.685	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	149.5	149.5	0

**Total Amount (a+b+c)**

3993.0408652

<b>Total GST (a)</b>	84.82061016
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	305.839610652
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	328.7775814509
<b>LABOUR CESS @ 1% (+)</b>	47.124786674629
<b>Grand Total</b>	4759.6034541375
<b>Say For Unit 1 (Grand Total/1)</b>	4759.6034541375

### Item 5

**R.C.C. Work (AR0404Aa):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	578.12	2007.984196	361.43715528
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
<b>LR008</b> : Sangi mulia	0.075	Per day	512	38.4	0

LR027 : Carpenter	0.075	Per day	562	42.15	0
-------------------	-------	---------	-----	-------	---

<b>b) Carriage Rate Details</b>						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	471.31	169.6716	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	471.31	254.5074	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	245.856	0.98465328	0	
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	245.856	0.226433376	0	

<b>c) Royalty Rate Details</b>						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0	
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0	

<b>Total Amount (a+b+c)</b>	5560.832862206
<b>Total GST (a)</b>	361.43715528
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	444.17025131145
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	477.48302015981
<b>LABOUR CESS @ 1% (+)</b>	68.439232889573
<b>Grand Total</b>	6912.3625218468
<b>Say For Unit 1 (Grand Total/1)</b>	6912.3625218468

<b>Item 6</b>
<b>R.C.C. Work (AR0404Ab):</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips****a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	578.12	2007.984196	361.43715528
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
<b>LR008</b> : Sangi mulia	0.25	Per day	512	128	0
<b>LR027</b> : Carpenter	0.25	Per day	562	140.5	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	471.31	169.6716	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	471.31	254.5074	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	245.856	3.2821776	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	245.856	0.75477792	0
--	---------	-------	---------	------------	---

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	6310.70835362
<b>Total GST (a)</b>	361.43715528
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	500.4109131675
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	537.94173165506
<b>LABOUR CESS @ 1% (+)</b>	77.104981537226
<b>Grand Total</b>	7787.6031352598
<b>Say For Unit 1 (Grand Total/1)</b>	7787.6031352598

**Item 7**

**R.C.C. Work (AR0404Ac):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0

<b>BRM340</b> : Cement	3.4733	1 Qntl.	578.12	2007.984196	361.43715528
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410d)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
<b>LR008</b> : Sangi mulia	5.23875	Per day	512	2682.24	0
<b>LR027</b> : Carpenter	5.23875	Per day	562	2944.1775	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	471.31	169.6716	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	471.31	254.5074	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	245.856	11.146865184	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	245.856	10.210153824	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	13540.723476518
<b>Total GST (a)</b>	361.43715528
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1042.6620473848
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1120.8617009387
<b>LABOUR CESS @ 1% (+)</b>	160.65684380122
<b>Grand Total</b>	16226.341223923
<b>Say For Unit 1 (Grand Total/1)</b>	16226.341223923

### Item 8

**R.C.C. Work (AR0404Ag):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	578.12	2007.984196	361.43715528
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410a)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0

LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	471.31	169.6716	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	471.31	254.5074	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	245.856	18.847075104	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	245.856	12.3461999232	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	11806.122323015
<b>Total GST (a)</b>	361.43715528
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	912.56696087214
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	981.00948293755
<b>LABOUR CESS @ 1% (+)</b>	140.61135922105
<b>Grand Total</b>	14201.747281326
<b>Say For Unit 1 (Grand Total/1)</b>	14201.747281326

**Item 9**

**R.C.C. Work (AR0409):** Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

**Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	7078.9	74328.45	13379.121

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

**Total Amount (a+b+c)**

81129.216

**Total GST (a)**

13379.121

**OVERHEAD CHARGES @ 7.5% (+)**

7088.125275

**CONTRACTOR PROFIT @ 7.5% (+)**

7619.734670625

**LABOUR CESS @ 1% (+)**

1092.1619694562

**Grand Total**

110308.35891508

**Say For Unit 1 (Grand Total/10)**

11030.835891508

**Item 10**

**Flooring (AR0802i):** 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

**2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0

<b>BRM340</b> : Cement	0.0858	1 Qntl.	578.12	49.602696	8.92848528
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	1396.62	32.12226	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0858	1 Qntl.	30.732	2.6368056	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.012	1 Cum	406.21	4.87452	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	536.41	12.33743	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0858	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.012	1 Cum	40.25	0.483	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	149.5	3.4385	0

<b>Total Amount (a+b+c)</b>	352.2977716
<b>Total GST (a)</b>	8.92848528
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	27.091969266
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	29.12386696095
<b>LABOUR CESS @ 1% (+)</b>	4.1744209310695
<b>Grand Total</b>	421.61651403802
<b>Say For Unit 1 (Grand Total/1)</b>	421.61651403802

#### Item 11

**Masonry Brick Work (AR0603di):** Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>LR002</b> : Female mulia	0.14	Per day	462	64.68	0
<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
<b>BRM001</b> : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance $\pm$ 8 percent.	350	1000 Nos	4.1	1435	0
<b>BRM340</b> : Cement	1	1 Qntl.	578.12	578.12	104.0616
<b>LR001</b> : Male mulia	2.82	Per day	462	1302.84	0
<b>LR025</b> : Mason	1.05	Per day	562	590.1	0
<b>LR044</b> : Mason	0.35	Per day	612	214.2	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM001</b> : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance $\pm$ 8 percent.	350	1000 Nos	1.011375	353.98125	0
<b>BRM340</b> : Cement	1	1 Qntl.	30.732	30.732	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	406.21	113.7388	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM001</b> : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance $\pm$ 8 percent.	350	1000 Nos	0.04025	14.0875	0
<b>BRM340</b> : Cement	1	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	40.25	11.27	0

<b>Total Amount (a+b+c)</b>	4763.27595
<b>Total GST (a)</b>	104.0616
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	365.05031625
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	392.42908996875
<b>LABOUR CESS @ 1% (+)</b>	56.248169562187
<b>Grand Total</b>	5681.0651257809
<b>Say For Unit 1 (Grand Total/1)</b>	5681.0651257809

**Pranya  
JE  
Tumudibandh Block**

**Saroj Kumar Sabat  
AEE  
Tumudibandh Block**

**BANABIHARI HARAPAL  
BDO  
Tumudibandh Block**