

Analysis

**OD/347/3312/116379/380626/00075684 : CONSTRUCTION OF CC ROAD FROM BARPADAR
TO SRIHARI NAGAR, GOBINDPUR
Block : Bargarh, Gram Panchayat : Gobindpur
Created By:BERCIUS DUNGUNG**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0110): Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.
Sub-Item of Work Fine dressing of earth work in ordinary or hard soil in road formation

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1	Per day	462	462	0
Total Amount (a+b+c)				462	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					34.65
CONTRACTOR PROFIT @ 7.5% (+)					37.24875

LABOUR CESS @ 1% (+)	5.3389875
Grand Total	539.2377375
Say For Unit 1 (Grand Total/100)	5.392377375

Item 3

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.3	6030	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	165.25	16525	0

Total Amount (a+b+c)	62376.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	4678.224
CONTRACTOR PROFIT @ 7.5% (+)	5029.0908
LABOUR CESS @ 1% (+)	720.836348
Grand Total	72804.471148
Say For Unit 1 (Grand Total/100)	728.04471148

Item 4

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	606.28	1388.3812	249.908616
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	67.93	32.6064	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	948.18	910.2528	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	406.21	389.9616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	165.25	79.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	249.5	239.52	0

Total Amount (a+b+c)	5177.11108
Total GST (a)	249.908616
OVERHEAD CHARGES @ 7.5% (+)	407.0264772
CONTRACTOR PROFIT @ 7.5% (+)	437.55346299
LABOUR CESS @ 1% (+)	62.7159963619
Grand Total	6334.3156325519
Say For Unit 1 (Grand Total/1)	6334.3156325519

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0

LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	606.28	1958.2844	352.491192
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	67.93	30.5685	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	165.25	74.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	249.5	224.55	0

Total Amount (a+b+c)	6670.43626
Total GST (a)	352.491192
OVERHEAD CHARGES @ 7.5% (+)	526.7195589
CONTRACTOR PROFIT @ 7.5% (+)	566.2235258175
LABOUR CESS @ 1% (+)	81.158705367175
Grand Total	8197.0292420847
Say For Unit 1 (Grand Total/1)	8197.0292420847

Item 6

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	160.570465023				
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972				
LABOUR CESS @ 1% (+)	24.741232485627				
Grand Total	2498.8644810484				
Say For Unit 1 (Grand Total/10)	249.88644810484				

Item 7

Earth Work (AR0102b): Earth work in hard soil or gravelly soil in embankment, roads etc. within 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the Department alongwith proper compaction with P.R.R. including hire and running charges of P.R.R. (section measurement to be taken on the finished compacted section of the fill) as per direction of Engineer-in-Charge.

Sub-Item of Work

Earth work in hard soil or gravelly soil in embankment, roads etc. within 50m initial lead and 1.5m initial lift and Compaction with P.R.R

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
PM024 : Smooth wheeled Roller 8 -10 tonne Soil compaction 70cum/hour	1.42857	per hour	524.7	749.570679	0
LR002 : Female mulia	21.5	Per day	462	9933	0
LR001 : Male mulia	21.5	Per day	462	9933	0

Total Amount (a+b+c)	20615.570679
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1546.167800925
CONTRACTOR PROFIT @ 7.5% (+)	1662.1303859944
LABOUR CESS @ 1% (+)	238.23868865919
Grand Total	24062.107554579
Say For Unit 1 (Grand Total/100)	240.62107554579

SAHEB PRADHAN
JE
Bargarh Block

SANTOSH KUMAR BEHERA
AEE
Bargarh Block

BERCIUS DUNGDUNG
BDO
Bargarh Block