

Analysis

**OD/361/3452/119470/386059/00069286 : Repair & Maintenance of Govt. Primary School,
Raisuan
Block : Kendujhar Sadar, Gram Panchayat : Raisuan
Created By:Binod Chandra Panda**

Item 1
Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	567.52	381.37344	68.6472192
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	28.354	19.053888	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	731.71	204.8788	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0.95245	333.3575	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0

BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

Total Amount (a+b+c)	4975.646128
Total GST (a)	68.6472192
OVERHEAD CHARGES @ 7.5% (+)	378.32200104
CONTRACTOR PROFIT @ 7.5% (+)	406.696151118
LABOUR CESS @ 1% (+)	58.29311499358
Grand Total	5887.6046143516
Say For Unit 1 (Grand Total/1)	5887.6046143516

Item 2

Plastering (AR1004i): 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in outside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	567.52	20.317216	3.65709888
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	65	0.975	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	28.354	1.0150732	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	731.71	10.97565	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	50.25	0.75375	0

Total Amount (a+b+c)	168.1566892
Total GST (a)	3.65709888
OVERHEAD CHARGES @ 7.5% (+)	12.886034106
CONTRACTOR PROFIT @ 7.5% (+)	13.85248666395
LABOUR CESS @ 1% (+)	1.9855230884995

Grand Total	200.53783193845
Say For Unit 1 (Grand Total/1)	200.53783193845

Item 3

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.28354	0.0354425	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.28354	0.025610064516129	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	159.13173804839
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.934880353629
CONTRACTOR PROFIT @ 7.5% (+)	12.829996380151
LABOUR CESS @ 1% (+)	1.8389661478217
Grand Total	185.73558092999
Say For Unit 1 (Grand Total/1)	185.73558092999

Item 4

Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.28354	0.70885	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)					780.63885
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					58.54791375
CONTRACTOR PROFIT @ 7.5% (+)					62.93900728125
LABOUR CESS @ 1% (+)					9.0212577103125
Grand Total					911.14702874156
Say For Unit 1 (Grand Total/10)					91.114702874156

Ratikanta Lenka
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block