

Analysis

OD/346/3305/116243/393096/00068193 : DEV OF SANGAMPUR PLAYGROUND

Block : Nilgiri, Gram Panchayat : Kanas

Created By: Bikram Kishore Parida

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0
Total Amount (a+b+c)				91240.32	
Total GST (a)				0	
OVERHEAD CHARGES @ 7.5% (+)				6843.024	
CONTRACTOR PROFIT @ 7.5% (+)				7356.2508	
LABOUR CESS @ 1% (+)				1054.395948	
Grand Total				106493.990748	
Say For Unit 1 (Grand Total/100)				1064.93990748	

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	42.622	97.60438	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	822.85	789.936	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	522.5	501.6	0

Total Amount (a+b+c)	5691.06918
-----------------------------	------------

Total GST (a)	221.43384
OVERHEAD CHARGES @ 7.5% (+)	443.4377265
CONTRACTOR PROFIT @ 7.5% (+)	476.6955559875
LABOUR CESS @ 1% (+)	68.326363024875
Grand Total	6900.9626655124
Say For Unit 1 (Grand Total/1)	6900.9626655124

Item 4

Flooring (AR0802ii): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	537.2	46.09176	8.2965168
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	1050	24.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	42.622	3.6569676	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	341.11	4.09332	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	822.85	18.92555	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	442.25	5.307	0

BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	522.5	12.0175	0
--	-------	-----------	-------	---------	---

Total Amount (a+b+c)	361.0446576
Total GST (a)	8.2965168
OVERHEAD CHARGES @ 7.5% (+)	27.70058808
CONTRACTOR PROFIT @ 7.5% (+)	29.778132186
LABOUR CESS @ 1% (+)	4.26819894666
Grand Total	431.08809361266
Say For Unit 1 (Grand Total/1)	431.08809361266

Item 5

Earth Work (AR0122Bii): Earthwork in hard soil or gravelly soil within 5 Km.mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.

Sub-Item of Work

Earthwork in hard soil or gravelly soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM402 : Loading into trucks and unloading from trucks within 50 Meter lead (2/3 of rate is consider for loading).	-0.6666	1 Cum	175.38	-	0
BRMM401 : Conveyance of material by 10 ton trucks within 5 KM including loading and unloading	1	1 Cum	276.01	276.01	0
LR002 : Female mulia	0.215	Per day	462	99.33	0
LR001 : Male mulia	0.215	Per day	462	99.33	0

Total Amount (a+b+c)	357.761692
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	26.8321269
CONTRACTOR PROFIT @ 7.5% (+)	28.8445364175
LABOUR CESS @ 1% (+)	4.134383553175
Grand Total	417.57273887067
Say For Unit 1 (Grand Total/1)	417.57273887067

Item 6

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	537.2	19.23176	3.4617168
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	42.622	1.5258676	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

Total Amount (a+b+c)	167.7812276
Total GST (a)	3.4617168
OVERHEAD CHARGES @ 7.5% (+)	12.84322083
CONTRACTOR PROFIT @ 7.5% (+)	13.80646239225
LABOUR CESS @ 1% (+)	1.9789262762225
Grand Total	199.87155389847
Say For Unit 1 (Grand Total/1)	199.87155389847

Item 7

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work
Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0

LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	537.2	360.9984	64.979712
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	42.622	28.641984	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.30585	457.0475	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5059.267584
Total GST (a)	64.979712
OVERHEAD CHARGES @ 7.5% (+)	384.3185472
CONTRACTOR PROFIT @ 7.5% (+)	413.14243824
LABOUR CESS @ 1% (+)	59.2170828144
Grand Total	5980.9253642544
Say For Unit 1 (Grand Total/1)	5980.9253642544

Item 8

miscellaneous (ARM286): Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.

Sub-Item of Work

Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.05	1 Cum	71.94	3.597	0
BRMM286 : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	485.28	485.28	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.05	1 Cum	341.11	17.0555	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.05	1 Cum	442.25	22.1125	0

Total Amount (a+b+c)	528.045				
Total GST (a)	0				
Grand Total	5980.9253642544				
Say For Unit 1 (Grand Total/1)	5980.9253642544				

Item 9

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	3.23	1 Qntl.	42.622	137.66906	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	822.85	740.565	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	522.5	470.25	0

Total Amount (a+b+c)	7235.06606
Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	566.0545605
CONTRACTOR PROFIT @ 7.5% (+)	608.5086525375
LABOUR CESS @ 1% (+)	87.219573530375
Grand Total	8809.1769265679
Say For Unit 1 (Grand Total/1)	8809.1769265679

MADHUSMITA MOHANTY
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block