

## Analysis

**OD/346/3309/116311/394015/00064844 : Repair & Maint. of AWC at Anantapur-3**  
**Block : Soro, Gram Panchayat : Antapur**  
**Created By:Satyanath Naik**

<b>Item 1</b>
<b>Dismantling (AR1612):</b> Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.
Sub-Item of Work <b>Dismantling and removing 2.5 cm. thick artificial stone flooring</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0
<b>Total Amount (a+b+c)</b>				924	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					69.3
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					74.4975
<b>LABOUR CESS @ 1% (+)</b>					10.677975
<b>Grand Total</b>					1078.475475
<b>Say For Unit 1 (Grand Total/9.3)</b>					115.96510483871

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	907.91	90791	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	100	1 Cum	442.25	44225	0
<b>Total Amount (a+b+c)</b>				147920.32	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				11094.024	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				11926.0758	
<b>LABOUR CESS @ 1% (+)</b>				1709.404198	
<b>Grand Total</b>				172649.823998	
<b>Say For Unit 1 (Grand Total/100)</b>				1726.49823998	

### Item 3

**Other Building Items. (AR1901Ba):** Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.

Sub-Item of Work  
**Vitrified Tile 600mmx600mm Coloured /Printed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM132</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	695.76	6957.6	0
<b>BRM174</b> : White Cement.	0.076	1Qntl	2017.18	153.30568	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	537.2	576.9528	103.851504
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
<b>LR001</b> : Male mulia	2.16	Per day	462	997.92	0
<b>LR044</b> : Mason	2.16	Per day	612	1321.92	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM132</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	9.6011111	96.011111	0
<b>BRM174</b> : White Cement.	0.076	1Qntl	24.787	1.883812	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	24.787	26.621238	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	907.91	190.6611	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM132</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	0	0	0
<b>BRM174</b> : White Cement.	0.076	1Qntl	0	0	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	442.25	92.8725	0

<b>Total Amount (a+b+c)</b>	10431.893041
<b>Total GST (a)</b>	103.851504
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	790.180840875
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	849.44440394063
<b>LABOUR CESS @ 1% (+)</b>	121.75369789816
<b>Grand Total</b>	12297.123487714
<b>Say For Unit 1 (Grand Total/10)</b>	1229.7123487714

**Raisen Murmu**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**