

Analysis

OD/346/3305/116241/393302/00068334 : Chandigarh Gandhahata Market Shed
Block : Nilgiri, Gram Panchayat : K.C.Pur
Created By: Bikram Kishore Parida

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	614.53	61453	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0
Total Amount (a+b+c)				118582.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				8893.674	
CONTRACTOR PROFIT @ 7.5% (+)				9560.69955	
LABOUR CESS @ 1% (+)				1370.3669355	
Grand Total				138407.0604855	
Say For Unit 1 (Grand Total/100)				1384.070604855	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	43.811	100.32719	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	614.53	294.9744	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	917.11	880.4256	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	522.5	501.6	0

Total Amount (a+b+c)				6134.51679	
-----------------------------	--	--	--	------------	--

Total GST (a)	224.929296
OVERHEAD CHARGES @ 7.5% (+)	476.95845645
CONTRACTOR PROFIT @ 7.5% (+)	512.73034068375
LABOUR CESS @ 1% (+)	73.491348831338
Grand Total	7422.6262319651
Say For Unit 1 (Grand Total/1)	7422.6262319651

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	545.68	366.69696	66.0054528
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	43.811	29.440992	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	614.53	172.0684	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.89485	663.1975	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0

BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

Total Amount (a+b+c)	5348.472752
Total GST (a)	66.0054528
OVERHEAD CHARGES @ 7.5% (+)	406.08586536
CONTRACTOR PROFIT @ 7.5% (+)	436.542305262
LABOUR CESS @ 1% (+)	62.57106375422
Grand Total	6319.6774391762
Say For Unit 1 (Grand Total/1)	6319.6774391762

Item 5

Plastering (AR1006): 12mm thick cement plaster (1:4) over brickwork in inside with cement punning for skirting/wall punning including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc. comp. and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:4) over brickwork in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.06	Per day	462	27.72	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.15	Per day	562	84.3	0
BRM340 : Cement	0.0644	1 Qntl.	545.68	35.141792	6.32552256
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0644	1 Qntl.	43.811	2.8214284	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	614.53	9.21795	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0644	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

Total Amount (a+b+c)	190.0881204
Total GST (a)	6.32552256
OVERHEAD CHARGES @ 7.5% (+)	14.731023222
CONTRACTOR PROFIT @ 7.5% (+)	15.83584996365
LABOUR CESS @ 1% (+)	2.2698051614565

Grand Total	229.25032130711
Say For Unit 1 (Grand Total/1)	229.25032130711

Item 6

Flooring (AR0802i): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	545.68	46.819344	8.42748192
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	1396.62	32.12226	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	43.811	3.7589838	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	614.53	7.37436	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	917.11	21.09353	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	442.25	5.307	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	522.5	12.0175	0

Total Amount (a+b+c)

375.2955378

Total GST (a)	8.42748192
OVERHEAD CHARGES @ 7.5% (+)	28.779226479
CONTRACTOR PROFIT @ 7.5% (+)	30.937668464925
LABOUR CESS @ 1% (+)	4.4343991466392
Grand Total	447.87431381056
Say For Unit 1 (Grand Total/1)	447.87431381056

Item 7

Roofing (AR1132i): Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge

Sub-Item of Work

Supplying, feeting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	333.12	3098.016	0
LR001 : Male mulia	2	Per day	462	924	0
LR047 : Fitter	1	Per day	612	612	0
LR045 : Carpenter	0.5	Per day	612	306	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	1.5978543	14.86004499	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	0	0	0

Total Amount (a+b+c)	4954.87604499
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	371.61570337425
CONTRACTOR PROFIT @ 7.5% (+)	399.48688112732
LABOUR CESS @ 1% (+)	57.259786294916
Grand Total	5783.2384157865
Say For Unit 1 (Grand Total/9.3)	621.85359309532

BAIDYANATH SINGH
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block