

Analysis

OD/346/3309/116311/394015/00064861 : Repair & Maint. of AWC at Anantapur-2
Block : Soro, Gram Panchayat : Antapur
Created By:Satyanath Naik

Item 1
Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.
Sub-Item of Work Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0
Total Amount (a+b+c)				924	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					69.3
CONTRACTOR PROFIT @ 7.5% (+)					74.4975
LABOUR CESS @ 1% (+)					10.677975
Grand Total					1078.475475
Say For Unit 1 (Grand Total/9.3)					115.96510483871

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	907.91	90791	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0
Total Amount (a+b+c)				147920.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				11094.024	
CONTRACTOR PROFIT @ 7.5% (+)				11926.0758	
LABOUR CESS @ 1% (+)				1709.404198	
Grand Total				172649.823998	
Say For Unit 1 (Grand Total/100)				1726.49823998	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	907.91	435.7968	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	536.41	514.9536	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	552.5	530.4	0

Total Amount (a+b+c)	5895.10223
-----------------------------	------------

Total GST (a)	224.929296
OVERHEAD CHARGES @ 7.5% (+)	459.00236445
CONTRACTOR PROFIT @ 7.5% (+)	493.42754178375
LABOUR CESS @ 1% (+)	70.724614322337
Grand Total	7143.1860465561
Say For Unit 1 (Grand Total/1)	7143.1860465561

Item 4

Other Building Items. (AR1901Ba): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.

Sub-Item of Work
Vitrified Tile 600mmx600mm Coloured /Printed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	695.76	6957.6	0
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	545.68	586.06032	105.4908576
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	9.6011111	96.011111	0
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM340 : Cement	1.074	1 Qntl.	24.787	26.621238	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	907.91	190.6611	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	10	1 Sqm.	0	0	0
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	442.25	92.8725	0

Total Amount (a+b+c)	10441.000561
Total GST (a)	105.4908576
OVERHEAD CHARGES @ 7.5% (+)	790.986856395
CONTRACTOR PROFIT @ 7.5% (+)	850.31087062462
LABOUR CESS @ 1% (+)	121.8778914562
Grand Total	12309.667037076
Say For Unit 1 (Grand Total/10)	1230.9667037076

Raisen Murmu
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block