

Analysis

**OD/366/3518/120505/427997/00065244 : Repair and Maintenance of Ram Temple at
Hirlaguda
Block : Nandahandi, Gram Panchayat : Mentri
Created By:Khirode Chandra Sahu**

Item 1
Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.
Sub-Item of Work Third floor

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.76228125	Per day	612	2302.516125	0
LR001 : Male mulia	3.76228125	Per day	462	1738.1739375	0
LR008 : Sangi mulia	8.79795	Per day	512	4504.5504	0
BRM340 : Cement	1.375	1 Qntl.	561	771.375	138.8475
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.13	11.4195	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	14.5102781	145.102781	0
BRM340 : Cement	1.375	1 Qntl.	42.622	58.60525	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	471.31	70.6965	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	40.25	6.0375	0

Total Amount (a+b+c)	16204.2769935
Total GST (a)	138.8475
OVERHEAD CHARGES @ 7.5% (+)	1225.7343370125
CONTRACTOR PROFIT @ 7.5% (+)	1317.6644122884
LABOUR CESS @ 1% (+)	188.86523242801
Grand Total	19075.388475229
Say For Unit 1 (Grand Total/10)	1907.5388475229

Item 2

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	561	1812.03	326.1654
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.13	34.2585	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	42.622	137.66906	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	471.31	424.179	0
--	-----	-----------	--------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	149.5	134.55	0

Total Amount (a+b+c)	6537.20656
Total GST (a)	326.1654
OVERHEAD CHARGES @ 7.5% (+)	514.752897
CONTRACTOR PROFIT @ 7.5% (+)	553.359364275
LABOUR CESS @ 1% (+)	79.31484221275
Grand Total	8010.7990634877
Say For Unit 1 (Grand Total/1)	8010.7990634877

Item 3

Other Building Items. (AR1911): Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge

Sub-Item of Work

Stainless steel of 304 grade in hand railing using 50mm dia of 2mm

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	0.89	Per day	512	455.68	0
LR047 : Fitter	0.89	Per day	612	544.68	0
BRMMR0024 : Buffing, Polishing etc.	1	L.S.	178.42	178.42	0
BRMMR0023 : Fabrication	34.16	kg	10	341.6	0
BRMMR0022 : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	16.63	kg	256.62	4267.5906	0
BRMMR0021 : Balustrade of size 30mmx32mmx2mm	6.12	kg	256.62	1570.5144	0
BRMMR0020 : Railing 50mm outer dia of 2mm thick	11.41	kg	240.24	2741.1384	0

Total Amount (a+b+c)	10099.6234
-----------------------------	------------

Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	757.471755
CONTRACTOR PROFIT @ 7.5% (+)	814.282136625
LABOUR CESS @ 1% (+)	116.71377291625
Grand Total	11788.091064541
Say For Unit 1 (Grand Total/3.26)	3615.9788541538

Item 4

Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0

Total Amount (a+b+c)	924
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	69.3
CONTRACTOR PROFIT @ 7.5% (+)	74.4975
LABOUR CESS @ 1% (+)	10.677975
Grand Total	1078.475475
Say For Unit 1 (Grand Total/9.3)	115.96510483871

SAUMYA RANJAN PANDA
JE
Nandahandi Block

SANKAR BUDEK
AEE
Nandahandi Block

Khirod Chandra Sahu
BDO
Nandahandi Block