

Analysis

**OD/369/3541/120969/410134/00075890 : CONSTRUCTION OF BRAHMAPADA WEST SIDE
GUARD WALL, BATHING STEPS AND CHANGING ROOM
Block : Kanas, Gram Panchayat : Alibada
Created By: SOUMYA RANJAN SWAIN**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.5	6050	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	705.67	70567	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	86352.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	6476.424				
CONTRACTOR PROFIT @ 7.5% (+)	6962.1558				
LABOUR CESS @ 1% (+)	997.908998				
Grand Total	100788.808798				
Say For Unit 1 (Grand Total/100)	1007.88808798				

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	548.03	1254.9887	225.897966
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75	36	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	36.677	83.99033	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	731.71	351.2208	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	731.71	702.4416	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	5250.30703
Total GST (a)	225.897966
OVERHEAD CHARGES @ 7.5% (+)	410.7153747
CONTRACTOR PROFIT @ 7.5% (+)	441.5190278025
LABOUR CESS @ 1% (+)	63.284393985025
Grand Total	6391.7237924875
Say For Unit 1 (Grand Total/1)	6391.7237924875

Item 4

Masonry Stone Work (AR0717): Laterite stone masonry in cement mortar (1:6) in foundation and plinth cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.

Sub-Item of Work
Laterite stone masonry

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	548.03	313.47316	56.4251688
LR001 : Male mulia	1.21	Per day	462	559.02	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.175	Per day	612	107.1	0
LR008 : Sangi mulia	1.41	Per day	512	721.92	0
LR052 : Stone dresser/ Cutter	2.12	Per day	612	1297.44	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	75	18	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	750.5	750.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	36.677	20.979244	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	731.71	175.6104	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	731.71	731.71	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	40.25	9.66	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	149.5	149.5	0

Total Amount (a+b+c)	5445.012804
Total GST (a)	56.4251688

OVERHEAD CHARGES @ 7.5% (+)	412.60784796
CONTRACTOR PROFIT @ 7.5% (+)	443.553436557
LABOUR CESS @ 1% (+)	63.57599257317
Grand Total	6421.1752498902
Say For Unit 1 (Grand Total/1)	6421.1752498902

Item 5

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	548.03	368.27616	66.2897088
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	75	21	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	36.677	24.646944	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	731.71	204.8788	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.89485	663.1975	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	40.25	11.27	0

BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

Total Amount (a+b+c)	5297.981904
Total GST (a)	66.2897088
OVERHEAD CHARGES @ 7.5% (+)	402.32037096
CONTRACTOR PROFIT @ 7.5% (+)	432.494398782
LABOUR CESS @ 1% (+)	61.99086382542
Grand Total	6261.0772463674
Say For Unit 1 (Grand Total/1)	6261.0772463674

Item 6

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work
Fourth Floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.6254935	Per day	462	1212.977997	0
LR044 : Mason	2.6254935	Per day	612	1606.802022	0
LR008 : Sangi mulia	6.685284375	Per day	512	3422.8656	0
BRM340 : Cement	2.737	1 Qntl.	548.03	1499.95811	269.9924598
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	75	9.75	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	21.0558341	210.558341	0
BRM340 : Cement	2.737	1 Qntl.	36.677	100.384949	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	731.71	95.1223	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	40.25	5.2325	0

Total Amount (a+b+c)	12749.451819
Total GST (a)	269.9924598
OVERHEAD CHARGES @ 7.5% (+)	976.45832091
CONTRACTOR PROFIT @ 7.5% (+)	1049.6926949782
LABOUR CESS @ 1% (+)	150.45595294688
Grand Total	15196.051247635
Say For Unit 1 (Grand Total/10)	1519.6051247635

Item 7
Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.
Sub-Item of Work 12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	548.03	19.619474	3.53150532
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	75	1.125	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	36.677	1.3130366	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	731.71	10.97565	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	40.25	0.60375	0

Total Amount (a+b+c)	167.7569106
Total GST (a)	3.53150532
OVERHEAD CHARGES @ 7.5% (+)	12.846631194
CONTRACTOR PROFIT @ 7.5% (+)	13.81012853355
LABOUR CESS @ 1% (+)	1.9794517564755
Grand Total	199.92462740403
Say For Unit 1 (Grand Total/1)	199.92462740403

Item 8

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	548.03	23.56529	4.2417522
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	75	1.35	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	36.677	1.577111	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	731.71	13.17078	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	40.25	0.7245	0

Total Amount (a+b+c)	241.187681
Total GST (a)	4.2417522
OVERHEAD CHARGES @ 7.5% (+)	18.40720749
CONTRACTOR PROFIT @ 7.5% (+)	19.78774805175
LABOUR CESS @ 1% (+)	2.8362438874175
Grand Total	286.46063262917
Say For Unit 1 (Grand Total/1)	286.46063262917

Item 9

Plastering (AR1008): 20mm thick cement Plaster in CM (1:6) for stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.057	1 Qntl.	548.03	31.23771	5.6227878
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	75	1.575	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	36.677	2.090589	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	731.71	15.36591	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	40.25	0.84525	0

Total Amount (a+b+c)

251.914459

Total GST (a)

5.6227878

OVERHEAD CHARGES @ 7.5% (+)

19.31529351

CONTRACTOR PROFIT @ 7.5% (+)

20.76394052325

LABOUR CESS @ 1% (+)

2.9761648083325

Grand Total

300.59264564158

Say For Unit 1 (Grand Total/1)

300.59264564158

Item 10

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.54512	0.425847744	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.660083744				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	49.6245062808				
CONTRACTOR PROFIT @ 7.5% (+)	53.34634425186				
LABOUR CESS @ 1% (+)	7.6463093427666				
Grand Total	772.27724361943				
Say For Unit 1 (Grand Total/9.3)	83.040563830046				

Item 11
Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
Sub-Item of Work Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.54512	1.3628	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM142 : Distemper	2.5	1 Kg.	0	0	0
--------------------	-----	-------	---	---	---

Total Amount (a+b+c)	781.2928
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	58.59696
CONTRACTOR PROFIT @ 7.5% (+)	62.991732
LABOUR CESS @ 1% (+)	9.02881492
Grand Total	911.91030692
Say For Unit 1 (Grand Total/10)	91.191030692

Item 12

Other Building Items. (AR1918): Supplying, fitting and fixing of Un-plasticised Poly Vinyl Chloride (UPVC) (FENESTA/NCL VEKA LTD) casement Door - 60 Series duly manufactured using UPVC reinforced profiles of 60mm x 55 mm x 2.5 mm for outer frames, 102 mm x 60 mm x 2.25mm for casement door Sash Profile and 74 mm x 60 mm x 2.5 mm mullion profile capable of mounting single glazing system structurally reinforced with hot dip galvanized up to 50 microns of minimum thickness of 2.0 mm prefabricated & welded through fusion welding the door sash shall be fitted with 12mm thick WPC Board of green ply make duly fixed with EPDM weathering seal resistant accessories like clipping locking system made of aluminium 1 no per set of sashes and the system is to be installed at the site using anchor fasteners, silicon rubber sealant, easy glazing/ deglazing at site etc, including cost and conveyance of all materials accessories, labour charges, materials and product conforming to ASTM D 638-14,EN-477-95 and other applicable codes and standards and as per direction of Engineer in Charge. (Rate given by Office of the Engineer-IN-Chief (Civil) Odisha Nirman Soudha Unit-V, Bhubaneswar vide letter no 16100 dated 08/05/2018)

Sub-Item of Work

UPVC Door with 12mm thick WPC Board

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM343 : UPVC Door conforming to ASTM D 638-14,EN-477-95 and other applicable codes and standards with 12mm thick WPC Board	1	Sqm	8963	8963	0

Total Amount (a+b+c)	8963
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	672.225
CONTRACTOR PROFIT @ 7.5% (+)	722.641875
LABOUR CESS @ 1% (+)	103.57866875
Grand Total	10461.44554375
Say For Unit 1 (Grand Total/1)	10461.44554375

GOPINATH PALAI
JE
Kanas Block

SASWAT KUMAR SENAPATI
AEE
Kanas Block

SOUMYA RANJAN SWAIN
BDO
Kanas Block