

## Analysis

**OD/370/3555/121231/426715/00075495 : Construction of C.C road from RD road to Gunam  
Bandha,Lachmanguda,Khilapadar  
Block : Padmapur, Gram Panchayat : Khilapadar  
Created By:KURESH CHANDRA JANI**

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

**Total Amount (a+b+c)**

23839.2

**Total GST (a)**

0

**OVERHEAD CHARGES @ 7.5% (+)**

1787.94

**CONTRACTOR PROFIT @ 7.5% (+)**

1922.0355

**LABOUR CESS @ 1% (+)**

275.491755

**Grand Total**

27824.667255

**Say For Unit 1 (Grand Total/100)**

278.24667255

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	471.31	47131	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	51.25	5125	0

Total Amount (a+b+c)	65160.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	4887.024				
CONTRACTOR PROFIT @ 7.5% (+)	5253.5508				
LABOUR CESS @ 1% (+)	753.008948				
Grand Total	76053.903748				
Say For Unit 1 (Grand Total/100)	760.53903748				

Item 3
<b>Concrete (AR0303a):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	569.96	1305.2084	234.937512
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	471.31	226.2288	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	51.25	24.6	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	158.5	152.16	0

<b>Total Amount (a+b+c)</b>	4788.15303
<b>Total GST (a)</b>	234.937512
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	376.73179065
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	404.98667494875
<b>LABOUR CESS @ 1% (+)</b>	58.048090075988
<b>Grand Total</b>	5862.8570976747
<b>Say For Unit 1 (Grand Total/1)</b>	5862.8570976747

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	569.96	1840.9708	331.374744
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	24.787	80.06201	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	51.25	23.0625	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	158.5	142.65	0

<b>Total Amount (a+b+c)</b>	6404.74781				
<b>Total GST (a)</b>	331.374744				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	505.20919155				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	543.09988091625				
<b>LABOUR CESS @ 1% (+)</b>	77.844316264662				
<b>Grand Total</b>	7862.2759427309				
<b>Say For Unit 1 (Grand Total/1)</b>	7862.2759427309				

**MANMOHAN SINGH**  
**JE**  
**Padmapur Block**

**SIMANCHAL DASH**  
**AEE**  
**Padmapur Block**

**KURESH CHANDRA JANI**  
**BDO**  
**Padmapur Block**