

## Analysis

**OD/372/3567/121436/419097/00071360 : Completion of CC of Tikra Pada, Seledi  
Block : Binka, Gram Panchayat : Seledi  
Created By:Sarat Kumar Bag**

### Item 1

**Plastering (AR1004):** 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**12mm thick cement plaster (1:6) over Brick work in inside**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	515.44	18.452752	3.32149536
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	36.677	1.3130366	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	170.25	2.55375	0

<b>Total Amount (a+b+c)</b>	162.7093886
<b>Total GST (a)</b>	3.32149536
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	12.452316297
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	13.386240019275
<b>LABOUR CESS @ 1% (+)</b>	1.9186944027628
<b>Grand Total</b>	193.78813467904
<b>Say For Unit 1 (Grand Total/1)</b>	193.78813467904

### Item 2

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

**Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0
<b>LR008</b> : Sangi mulia	7.6	Per day	512	3891.2	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	515.44	708.73	127.5714
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	12.8738891	128.738891	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	36.677	50.430875	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	170.25	25.5375	0

**Total Amount (a+b+c)**

14953.635766

**Total GST (a)**

127.5714

**OVERHEAD CHARGES @ 7.5% (+)**

1131.09053745

<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1215.9223277588
<b>LABOUR CESS @ 1% (+)</b>	174.28220031209
<b>Grand Total</b>	17602.502231521
<b>Say For Unit 1 (Grand Total/10)</b>	1760.2502231521

### Item 3

**Flooring (AR0817b):** Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

**Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM129</b> : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405.2	4052	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	515.44	708.73	127.5714
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM129</b> : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	12.8738891	128.738891	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	36.677	50.430875	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM129</b> : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	170.25	25.5375	0

<b>Total Amount (a+b+c)</b>	8518.635766
<b>Total GST (a)</b>	127.5714
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	648.46553745
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	697.10045275875
<b>LABOUR CESS @ 1% (+)</b>	99.917731562087
<b>Grand Total</b>	10091.690887771
<b>Say For Unit 1 (Grand Total/10)</b>	1009.1690887771

#### Item 4

**Iron Work (AR1704):** Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work  
**Iron Doors and windows fixing**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM341 : Steel</b>	0.508	1 Qntl.	6215.96	3157.70768	568.3873824
<b>LR001 : Male mulia</b>	3.25	Per day	462	1501.5	0
<b>LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder</b>	1	Per day	512	512	0
<b>LR028 : Fitter</b>	1	Per day	562	562	0
<b>LR047 : Fitter</b>	1	Per day	612	612	0
<b>LR026 : Black smith</b>	1	Per day	562	562	0
<b>LR046 : Blacksmith</b>	0.75	Per day	612	459	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM341 : Steel</b>	0.508	1 Qntl.	36.677	18.631916	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM341 : Steel</b>	0.508	1 Qntl.	0	0	0

<b>Total Amount (a+b+c)</b>	7384.839596
<b>Total GST (a)</b>	568.3873824
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	596.49202338
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	641.2289251335

<b>LABOUR CESS @ 1% (+)</b>	91.909479269135
<b>Grand Total</b>	9282.8574061826
<b>Say For Unit 1 (Grand Total/0.508)</b>	18273.341350753

### Item 5

**Plastering (AR1014):** 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work  
**16mm thick cement Plaster in CM (1:6) over brick work in inside.**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	515.44	22.16392	3.9895056
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	36.677	1.577111	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	170.25	3.0645	0

<b>Total Amount (a+b+c)</b>	235.129351
<b>Total GST (a)</b>	3.9895056
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	17.933914245
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	19.278957813375
<b>LABOUR CESS @ 1% (+)</b>	2.7633172865838
<b>Grand Total</b>	279.09504594496
<b>Say For Unit 1 (Grand Total/1)</b>	279.09504594496

### Item 6

**Painting (AR0920):** Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

**Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.36677	0.4584625	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

**Total Amount (a+b+c)**

938.2934625

**Total GST (a)**

0

**OVERHEAD CHARGES @ 7.5% (+)**

70.3720096875

**CONTRACTOR PROFIT @ 7.5% (+)**

75.649910414063

**LABOUR CESS @ 1% (+)**

10.843153826016

**Grand Total**

1095.1585364276

**Say For Unit 1 (Grand Total/10)**

109.51585364276

**Item 7**

**Painting (AR0918cb):** Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

**Finishing wall two coats with weather coat with one coat waterbound Primer**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918f)</b>					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0

**Combine :: Painting (AR0901di)**

<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
<b>LR048</b> : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
<b>LR001</b> : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0.36677	0.04584625	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.36677	0.033127612903226	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	159.14965934677
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	11.936224451008
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	12.831441284834
<b>LABOUR CESS @ 1% (+)</b>	1.8391732508262
<b>Grand Total</b>	185.75649833344
<b>Say For Unit 1 (Grand Total/1)</b>	185.75649833344

**DIKAN KUMAR KHARSEL**  
**JE**  
**Binka Block**

**BIJAY PURTY**  
**AEE**  
**Binka Block**

**Sarat Kumar Bag**  
**BDO**  
**Binka Block**