

Analysis

OD/345/3292/115928/421465/00063627 : CONST OF VANA SURAKSHA SAMITI BUILDING AT DANGABANJI

Block : Muribahal, Gram Panchayat : Malisira

Created By:Basanti Sethy

Item 1
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	504.18	1154.5722	207.822996
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	43.25	20.76	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	158.5	152.16	0

Total Amount (a+b+c)	4770.75523
Total GST (a)	207.822996
OVERHEAD CHARGES @ 7.5% (+)	373.39336695
CONTRACTOR PROFIT @ 7.5% (+)	401.39786947125
LABOUR CESS @ 1% (+)	57.533694624213

Grand Total	5810.9031570455
Say For Unit 1 (Grand Total/1)	5810.9031570455

Item 2

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	504.18	18.049644	3.24893592
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	43.25	0.64875	0

Total Amount (a+b+c)	160.1884496
Total GST (a)	3.24893592
OVERHEAD CHARGES @ 7.5% (+)	12.257803914
CONTRACTOR PROFIT @ 7.5% (+)	13.17713920755
LABOUR CESS @ 1% (+)	1.8887232864155
Grand Total	190.76105192797
Say For Unit 1 (Grand Total/1)	190.76105192797

Item 3

R.C.C. Work (AR0410e): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm

Sub-Item of Work
Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	2.1	1Mtr.	41.81	87.801	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	58374.79	2410.878827	0
LR008 : Sangi mulia	1.25	Per day	512	640	0
LR027 : Carpenter	1.25	Per day	562	702.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0276	1Mtr.	198.296	5.4729696	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	198.296	8.1896248	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0276	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	0	0	0

Total Amount (a+b+c)	3854.8424214
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	289.113181605
CONTRACTOR PROFIT @ 7.5% (+)	310.79667022538
LABOUR CESS @ 1% (+)	44.547522732304
Grand Total	4499.2997959627
Say For Unit 1 (Grand Total/7.8)	576.8333071747

Item 4

R.C.C. Work (AR0410a): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height

Sub-Item of Work
Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	5.6	1Mtr	51.87	290.472	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	58374.79	2638.540508	0

LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	198.296	13.682424	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	198.296	8.9629792	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	0	0	0

Total Amount (a+b+c)	5905.1579112
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	442.88684334
CONTRACTOR PROFIT @ 7.5% (+)	476.1033565905
LABOUR CESS @ 1% (+)	68.241481111305
Grand Total	6892.3895922418
Say For Unit 1 (Grand Total/9)	765.82106580465

Item 5

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6175.4	64841.7	11671.506

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	71579.2435				
Total GST (a)	11671.506				
OVERHEAD CHARGES @ 7.5% (+)	6243.8062125				
CONTRACTOR PROFIT @ 7.5% (+)	6712.0916784375				
LABOUR CESS @ 1% (+)	962.06647390937				
Grand Total	97168.713864847				
Say For Unit 1 (Grand Total/10)	9716.8713864847				

Item 6

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	504.18	693.2475	124.78455
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.6011111	96.011111	0

BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	43.25	6.4875	0

Total Amount (a+b+c)	14870.026736
Total GST (a)	124.78455
OVERHEAD CHARGES @ 7.5% (+)	1124.61084645
CONTRACTOR PROFIT @ 7.5% (+)	1208.9566599337
LABOUR CESS @ 1% (+)	173.28378792384
Grand Total	17501.662580308
Say For Unit 1 (Grand Total/10)	1750.1662580308

Item 7

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0

BRM340 : Cement	2.737	1 Qntl.	504.18	1379.94066	248.3893188
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	9.6011111	96.011111	0
BRM340 : Cement	2.737	1 Qntl.	24.787	67.842019	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	341.11	44.3443	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	43.25	5.6225	0

Total Amount (a+b+c)	11325.39499
Total GST (a)	248.3893188
OVERHEAD CHARGES @ 7.5% (+)	868.03382316
CONTRACTOR PROFIT @ 7.5% (+)	933.136359897
LABOUR CESS @ 1% (+)	133.74954491857
Grand Total	13508.704036776
Say For Unit 1 (Grand Total/10)	1350.8704036776

Item 8

R.C.C. Work (AR0404A): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0

PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	504.18	1751.168394	315.21031092
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	43.25	19.4625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	158.5	57.06	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	158.5	85.59	0

Total Amount (a+b+c)	4818.2468811
Total GST (a)	315.21031092
OVERHEAD CHARGES @ 7.5% (+)	385.0092894015
CONTRACTOR PROFIT @ 7.5% (+)	413.88498610661

LABOUR CESS @ 1% (+)	59.323514675281
Grand Total	5991.6749822034
Say For Unit 1 (Grand Total/1)	5991.6749822034

Item 9

Earth Work (AR0122Aia): Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge

Sub-Item of Work

Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	28.41204	Per day	462	13126.36248	0
LR001 : Male mulia	28.41204	Per day	462	13126.36248	0

Total Amount (a+b+c)	26252.72496
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1968.954372
CONTRACTOR PROFIT @ 7.5% (+)	2116.6259499
LABOUR CESS @ 1% (+)	303.383052819
Grand Total	30641.688334719
Say For Unit 1 (Grand Total/100)	306.41688334719

Item 10

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0

LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	504.18	338.80896	60.9856128
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.1586	405.51	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	43.25	12.11	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	4894.835524
Total GST (a)	60.9856128
OVERHEAD CHARGES @ 7.5% (+)	371.68658526
CONTRACTOR PROFIT @ 7.5% (+)	399.5630791545
LABOUR CESS @ 1% (+)	57.270708012145
Grand Total	5784.3415092266
Say For Unit 1 (Grand Total/1)	5784.3415092266

Item 11

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0

BRM340 : Cement	0.0372	1 Qntl.	504.18	18.755496	3.37598928
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	76.88	0.5766	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	341.11	2.558325	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	43.25	0.324375	0

Total Amount (a+b+c)	180.3568724
Total GST (a)	3.37598928
OVERHEAD CHARGES @ 7.5% (+)	13.779964626
CONTRACTOR PROFIT @ 7.5% (+)	14.81346197295
LABOUR CESS @ 1% (+)	2.1232628827895
Grand Total	214.44955116174
Say For Unit 1 (Grand Total/1)	214.44955116174

Item 12

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	504.18	21.67974	3.9023532
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	43.25	0.7785	0

Total Amount (a+b+c)	231.847901
Total GST (a)	3.9023532
OVERHEAD CHARGES @ 7.5% (+)	17.681269065
CONTRACTOR PROFIT @ 7.5% (+)	19.007364244875
LABOUR CESS @ 1% (+)	2.7243888750988
Grand Total	275.16327638497
Say For Unit 1 (Grand Total/1)	275.16327638497

Item 13
Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
Sub-Item of Work Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.24787	0.619675	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	780.549675
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	58.541225625
CONTRACTOR PROFIT @ 7.5% (+)	62.931817546875
LABOUR CESS @ 1% (+)	9.0202271817188
Grand Total	911.04294535359
Say For Unit 1 (Grand Total/10)	91.104294535359

Item 14

Concrete (AR0317): 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)

Sub-Item of Work

2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.36	Per day	462	166.32	0
LR044 : Mason	0.1	Per day	612	61.2	0
BRM340 : Cement	0.1208	1 Qntl.	504.18	60.904944	10.96288992
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	76.88	1.299272	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	850.2	14.36838	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	24.787	2.9942696	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	341.11	5.764759	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	341.11	5.764759	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	43.25	0.730925	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	158.5	2.67865	0

Total Amount (a+b+c)

322.0259586

Total GST (a)

10.96288992

OVERHEAD CHARGES @ 7.5% (+)

24.974163639

CONTRACTOR PROFIT @ 7.5% (+)

26.847225911925

LABOUR CESS @ 1% (+)

3.8481023807093

Grand Total

388.65834045163

Say For Unit 1 (Grand Total/1)	388.65834045163
--------------------------------	-----------------

Item 15

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	43.25	4325	0

Total Amount (a+b+c)	51340.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	3850.524
CONTRACTOR PROFIT @ 7.5% (+)	4139.3133
LABOUR CESS @ 1% (+)	593.301573
Grand Total	59923.458873
Say For Unit 1 (Grand Total/100)	599.23458873

Item 16

Masonry Brick Work (AR0603c): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0

BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	504.18	338.80896	60.9856128
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0.92692	370.768	0
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	43.25	12.11	0

Total Amount (a+b+c)	4849.153024
Total GST (a)	60.9856128
OVERHEAD CHARGES @ 7.5% (+)	368.26039776
CONTRACTOR PROFIT @ 7.5% (+)	395.879927592
LABOUR CESS @ 1% (+)	56.74278962152
Grand Total	5731.0217517735
Say For Unit 1 (Grand Total/1)	5731.0217517735

Item 17

R.C.C. Work (AR0410d): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm

Sub-Item of Work

Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	2.32	1Mtr	51.87	120.3384	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	58374.79	1272.570422	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	198.296	4.7194448	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	198.296	4.3228528	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	0	0	0

Total Amount (a+b+c)	4355.4511196
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	326.65883397
CONTRACTOR PROFIT @ 7.5% (+)	351.15824651775
LABOUR CESS @ 1% (+)	50.332682000878
Grand Total	5083.6008820886
Say For Unit 1 (Grand Total/4.2)	1210.3811624021

Item 18

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0
--	--------	-------	---------	-------------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	49.6070904033
CONTRACTOR PROFIT @ 7.5% (+)	53.327622183548
LABOUR CESS @ 1% (+)	7.6436258463085
Grand Total	772.00621047716
Say For Unit 1 (Grand Total/9.3)	83.011420481415

Item 19
Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
Sub-Item of Work Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.24787	0.288148875	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.195898875
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	113.41469241562
CONTRACTOR PROFIT @ 7.5% (+)	121.9207943468
LABOUR CESS @ 1% (+)	17.475313856374
Grand Total	1765.0066994938

Say For Unit 1 (Grand Total/9.3)	189.78566661224
---	-----------------

Item 20

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.24787	0.3098375	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)	938.1448375
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	70.3608628125
CONTRACTOR PROFIT @ 7.5% (+)	75.637927523437
LABOUR CESS @ 1% (+)	10.841436278359
Grand Total	1094.9850641143
Say For Unit 1 (Grand Total/10)	109.49850641143

GITANJALI SAHU
JE
Muribahal Block

Abinash Mudi
AEE
Muribahal Block

Basanti Sethy
BDO
Muribahal Block