

Analysis

OD/365/3498/120229/388889/00069107 : DRAINAGE SYSTEM AT KANKADA VILLAGE
Block : Karanjia, Gram Panchayat : Tato
Created By:PRADYUMNA KUMAR NAYAK

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.43	6043	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	796.81	79681	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	283.25	28325	0

Total Amount (a+b+c)	119759.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	8981.949				
CONTRACTOR PROFIT @ 7.5% (+)	9655.595175				
LABOUR CESS @ 1% (+)	1383.96864175				
Grand Total	139780.83281675				
Say For Unit 1 (Grand Total/100)	1397.8083281675				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	608	1392.32	250.6176
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.85	32.088	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	796.81	382.4688	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	575.47	552.4512	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	283.25	135.96	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	338.5	324.96	0

Total Amount (a+b+c)	5749.02428				
-----------------------------	------------	--	--	--	--

Total GST (a)	250.6176
OVERHEAD CHARGES @ 7.5% (+)	449.973141
CONTRACTOR PROFIT @ 7.5% (+)	483.721126575
LABOUR CESS @ 1% (+)	69.33336147575
Grand Total	7002.6695090508
Say For Unit 1 (Grand Total/1)	7002.6695090508

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2142.50140404
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.687605303
CONTRACTOR PROFIT @ 7.5% (+)	172.73917570073
LABOUR CESS @ 1% (+)	24.759281850437
Grand Total	2500.6874668942
Say For Unit 1 (Grand Total/10)	250.06874668942

Item 5

R.C.C. Work (AR0404Bg): Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404B)					
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1380	496.8	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	608	2111.7664	380.117952
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.85	30.0825	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	575.47	207.1692	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	575.47	310.7538	0
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	796.81	358.5645	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	245.856	18.847075104	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	245.856	12.3461999232	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	338.5	121.86	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	338.5	182.79	0
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	283.25	127.4625	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

Total Amount (a+b+c)	12440.433827015
Total GST (a)	380.117952
OVERHEAD CHARGES @ 7.5% (+)	961.54138342614
CONTRACTOR PROFIT @ 7.5% (+)	1033.6569871831
LABOUR CESS @ 1% (+)	148.15750149624
Grand Total	14963.907651121
Say For Unit 1 (Grand Total/1)	14963.907651121

Item 6

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0

LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	608	1963.84	353.4912
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.85	30.0825	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	796.81	358.5645	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	575.47	517.923	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	283.25	127.4625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	338.5	304.65	0

Total Amount (a+b+c)	7166.10486
Total GST (a)	353.4912
OVERHEAD CHARGES @ 7.5% (+)	563.9697045
CONTRACTOR PROFIT @ 7.5% (+)	606.2674323375
LABOUR CESS @ 1% (+)	86.898331968375
Grand Total	8776.7315288059
Say For Unit 1 (Grand Total/1)	8776.7315288059

Item 7

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6176.71	64855.455	11673.9819

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	71655.421
Total GST (a)	11673.9819
OVERHEAD CHARGES @ 7.5% (+)	6249.7052175
CONTRACTOR PROFIT @ 7.5% (+)	6718.4331088125
LABOUR CESS @ 1% (+)	962.97541226313
Grand Total	97260.516638576
Say For Unit 1 (Grand Total/10)	9726.0516638576

Item 8

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	608	22.6176	4.071168

BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	66.85	0.501375	0
--	--------	-------	-------	----------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	30.732	1.1432304	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	796.81	5.976075	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	283.25	2.124375	0

Total Amount (a+b+c)	189.5826554
Total GST (a)	4.071168
OVERHEAD CHARGES @ 7.5% (+)	14.524036755
CONTRACTOR PROFIT @ 7.5% (+)	15.613339511625
LABOUR CESS @ 1% (+)	2.2379119966663
Grand Total	226.02911166329
Say For Unit 1 (Grand Total/1)	226.02911166329

PRATAP
JE
Karanjia Block

LOKANATH NAIK
AEE
Karanjia Block

PRADYUMNA KUMAR NAYAK
BDO
Karanjia Block