

Analysis

OD/369/3541/275296/410139/00075784 : CC ROAD AND GARD WALL FROM GP OFFICE
Block : Kanas, Gram Panchayat : Gadisagoda
Created By: SOUMYA RANJAN SWAIN

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.5	6050	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	679.63	67963	0

c) Royalty Rate Details					

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	75.25	7525	0
Total Amount (a+b+c)				87248.32	
Total GST (a)				0	
OVERHEAD CHARGES @ 7.5% (+)				6543.624	
CONTRACTOR PROFIT @ 7.5% (+)				7034.3958	
LABOUR CESS @ 1% (+)				1008.263398	
Grand Total				101834.603198	
Say For Unit 1 (Grand Total/100)				1018.34603198	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	548.03	1254.9887	225.897966
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75	36	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	36.677	83.99033	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	679.63	326.2224	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	835.87	802.4352	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75.25	36.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	309.5	297.12	0

Total Amount (a+b+c)	5695.27663
-----------------------------	------------

Total GST (a)	225.897966
OVERHEAD CHARGES @ 7.5% (+)	444.0880947
CONTRACTOR PROFIT @ 7.5% (+)	477.3947018025
LABOUR CESS @ 1% (+)	68.426573925025
Grand Total	6911.0839664275
Say For Unit 1 (Grand Total/1)	6911.0839664275

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	293.416	7.8342072	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	293.416	1.80157424	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2144.06327444
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.804745583
CONTRACTOR PROFIT @ 7.5% (+)	172.86510150173
LABOUR CESS @ 1% (+)	24.777331215247
Grand Total	2502.51045274
Say For Unit 1 (Grand Total/10)	250.251045274

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	548.03	1770.1369	318.624642
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75	33.75	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1372.71	1235.439	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	36.677	118.46671	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	679.63	305.8335	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	835.87	752.283	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75.25	33.8625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	309.5	278.55	0

Total Amount (a+b+c)

7035.68161

Total GST (a)

318.624642

OVERHEAD CHARGES @ 7.5% (+)	551.5729689
CONTRACTOR PROFIT @ 7.5% (+)	592.9409415675
LABOUR CESS @ 1% (+)	84.988201624675
Grand Total	8583.8083640922
Say For Unit 1 (Grand Total/1)	8583.8083640922

SONIA RANI SAHOO
JE
Kanas Block

SASWAT KUMAR SENAPATI
AEE
Kanas Block

SOUMYA RANJAN SWAIN
BDO
Kanas Block