

Analysis

OD/361/3450/119416/385521/00070931 : TOILET REPAIRING, ACR GRADING, FLOORING & COLORING AT GOVT.UPS RAJABASA
Block : Jhumpura, Gram Panchayat : Balibandha
Created By:KendujharJhumpuraBDO

Item 1
Dismantling (AR1603): Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.
Sub-Item of Work Dismantling brick or stone masonry under 3m.

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	4.5	Per day	462	2079	0
LR001 : Male mulia	4	Per day	462	1848	0
Total Amount (a+b+c)				3927	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				294.525	
CONTRACTOR PROFIT @ 7.5% (+)				316.614375	
LABOUR CESS @ 1% (+)				45.38139375	
Grand Total				4583.52076875	
Say For Unit 1 (Grand Total/2.83)				1619.6186462014	

Item 2
Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0

LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.16	372.39552	67.0311936
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	36.677	24.646944	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	1091.91	305.7348	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.89485	663.1975	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5402.957264
Total GST (a)	67.0311936
OVERHEAD CHARGES @ 7.5% (+)	410.24913432
CONTRACTOR PROFIT @ 7.5% (+)	441.017819394
LABOUR CESS @ 1% (+)	63.21255411314
Grand Total	6384.4679654271
Say For Unit 1 (Grand Total/1)	6384.4679654271

Item 3

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0

LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	554.16	19.838928	3.57100704
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	65	0.975	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	36.677	1.3130366	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	1091.91	16.37865	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	50.25	0.75375	0

Total Amount (a+b+c)	173.3793646
Total GST (a)	3.57100704
OVERHEAD CHARGES @ 7.5% (+)	13.271277873
CONTRACTOR PROFIT @ 7.5% (+)	14.266623713475
LABOUR CESS @ 1% (+)	2.0448827322648
Grand Total	206.53315595874
Say For Unit 1 (Grand Total/1)	206.53315595874

Item 4

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.36677	0.04584625	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.36677	0.033127612903226	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	159.14965934677
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.936224451008
CONTRACTOR PROFIT @ 7.5% (+)	12.831441284834
LABOUR CESS @ 1% (+)	1.8391732508262
Grand Total	185.75649833344
Say For Unit 1 (Grand Total/1)	185.75649833344

Item 5

Iron Work (AR1703): Iron work wrought and put up in trusses and record racks including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.

Sub-Item of Work

Iron work wrought and put up in trusses and record racks

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6841.58	3475.52264	625.5940752
LR001 : Male mulia	2.5	Per day	462	1155	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR026 : Black smith	1.25	Per day	562	702.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	36.677	18.631916	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	6425.654556
Total GST (a)	625.5940752
OVERHEAD CHARGES @ 7.5% (+)	528.84364734
CONTRACTOR PROFIT @ 7.5% (+)	568.5069208905
LABOUR CESS @ 1% (+)	81.485991994305
Grand Total	8230.0851914248
Say For Unit 1 (Grand Total/0.508)	16200.95510123

Item 6

Roofing (AR1132i): Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge

Sub-Item of Work

Supplying, feeting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	333.12	3098.016	0
LR001 : Male mulia	2	Per day	462	924	0
LR047 : Fitter	1	Per day	612	612	0
LR045 : Carpenter	0.5	Per day	612	306	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	1.2066733	11.22206169	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	0	0	0

Total Amount (a+b+c)	4951.23806169
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	371.34285462675
CONTRACTOR PROFIT @ 7.5% (+)	399.19356872376
LABOUR CESS @ 1% (+)	57.217744850405
Grand Total	5778.9922298909
Say For Unit 1 (Grand Total/9.3)	621.39701396676

Item 7

Flooring (AR0816k): Fixing Ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .

Sub-Item of Work

Fixing Ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor (For repair and maintenance) .

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	554.16	1516.73592	273.0124656
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	65	8.45	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	21.0558341	210.558341	0
BRM340 : Cement	2.737	1 Qntl.	36.677	100.384949	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	1091.91	141.9483	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	50.25	6.5325	0

Total Amount (a+b+c)

11706.25001

Total GST (a)

273.0124656

OVERHEAD CHARGES @ 7.5% (+)

898.44468567

CONTRACTOR PROFIT @ 7.5% (+)	965.82803709525
LABOUR CESS @ 1% (+)	138.43535198365
Grand Total	13981.970550349
Say For Unit 1 (Grand Total/10)	1398.1970550349

Item 8

Flooring (AR0817bk): Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles, including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .

Sub-Item of Work

Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3)(For repair and maintenance)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405.2	4052	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	554.16	761.97	137.1546
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	65	9.75	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	21.0558341	210.558341	0
BRM340 : Cement	1.375	1 Qntl.	36.677	50.430875	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	1091.91	163.7865	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	50.25	7.5375	0
Total Amount (a+b+c)	8746.533216				
Total GST (a)	137.1546				
OVERHEAD CHARGES @ 7.5% (+)	666.2765862				
CONTRACTOR PROFIT @ 7.5% (+)	716.247330165				
LABOUR CESS @ 1% (+)	102.66211732365				
Grand Total	10368.873849689				
Say For Unit 1 (Grand Total/10)	1036.8873849689				

Ajay Kumar Behera
JE
Jhumpura Block

SIDA MAJHEE
AEE
Jhumpura Block

KendujharJhumpuraBDO
BDO
Jhumpura Block