

Analysis

**OD/362/3458/119569/408334/00070328 : PRESERVATION AND DEVELOPMENT OF TANK AT
KHAJURIA OF GAMBHARIMUNDA
Block : Banapur, Gram Panchayat : Gambharimunda
Created By:Sri Bikash Kumar Mohanty**

Item 1
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	544.6	1247.134	224.48412
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.58	30.0384	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	1045.91	502.0368	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	907.91	871.5936	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	5728.80503
Total GST (a)	224.48412
OVERHEAD CHARGES @ 7.5% (+)	446.49668625
CONTRACTOR PROFIT @ 7.5% (+)	479.98393771875
LABOUR CESS @ 1% (+)	68.797697739687

Grand Total	6948.5674717084
Say For Unit 1 (Grand Total/1)	6948.5674717084

Item 2

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)	23839.2
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1787.94
CONTRACTOR PROFIT @ 7.5% (+)	1922.0355
LABOUR CESS @ 1% (+)	275.491755
Grand Total	27824.667255
Say For Unit 1 (Grand Total/100)	278.24667255

Item 3

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	55975.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	4198.149
CONTRACTOR PROFIT @ 7.5% (+)	4513.010175
LABOUR CESS @ 1% (+)	646.86479175
Grand Total	65333.34396675
Say For Unit 1 (Grand Total/100)	653.3334396675

Item 4

Masonry Stone Work (AR0717i): Laterite stone masonry in cement mortar (1:6) in superstructure cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.

Sub-Item of Work

Laterite stone masonry in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0026 : SCAFFOLDING CHARGES FOR LATERITE STONE MASONRY WORK	1	1 Cum	41.9	41.9	0
BRM340 : Cement	0.572	1 Qntl.	544.6	311.5112	56.072016
LR001 : Male mulia	1.21	Per day	462	559.02	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.175	Per day	612	107.1	0
LR008 : Sangi mulia	1.41	Per day	512	721.92	0
LR052 : Stone dresser/ Cutter	2.12	Per day	612	1297.44	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	62.58	15.0192	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	729.98	729.98	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	24.787	14.178164	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	1045.91	251.0184	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	796.81	796.81	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	40.25	9.66	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	149.5	149.5	0
Total Amount (a+b+c)					5595.156964
Total GST (a)					56.072016
OVERHEAD CHARGES @ 7.5% (+)					423.8421735
CONTRACTOR PROFIT @ 7.5% (+)					455.6303365125
LABOUR CESS @ 1% (+)					65.307014900125
Grand Total					6596.0085049126
Say For Unit 1 (Grand Total/1)					6596.0085049126

Item 5

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)					2140.93953364
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					160.570465023

CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 6

Plastering (AR1008): 20mm thick cement Plaster in CM (1:6) for stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.057	1 Qntl.	544.6	31.0422	5.587596
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	62.58	1.31418	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	24.787	1.412859	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	1045.91	21.96411	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	40.25	0.84525	0

Total Amount (a+b+c)	257.378599
Total GST (a)	5.587596
OVERHEAD CHARGES @ 7.5% (+)	19.722464625
CONTRACTOR PROFIT @ 7.5% (+)	21.201649471875
LABOUR CESS @ 1% (+)	3.0389030909688
Grand Total	306.92921218784
Say For Unit 1 (Grand Total/1)	306.92921218784

ramesh chandra mahapatra
JE
Banapur Block

SURESH MALIK
AEE
Banapur Block

Sri Bikash Kumar Mohanty
BDO
Banapur Block