

Analysis

**OD/365/3488/120067/387559/00067620 : Repair & Maintenance of AWC Building at Gunduria
Block : Bahalda, Gram Panchayat : Anlajodi
Created By:MayurbhanjBahaldaBDO**

Item 1
Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.
Sub-Item of Work Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0
Total Amount (a+b+c)				924	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					69.3
CONTRACTOR PROFIT @ 7.5% (+)					74.4975
LABOUR CESS @ 1% (+)					10.677975
Grand Total					1078.475475
Say For Unit 1 (Grand Total/9.3)					115.96510483871

Item 2
Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)
Sub-Item of Work Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	608	652.992	117.53856
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	66.85	14.0385	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0

LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	48.567	3.691092	0
BRM340 : Cement	1.074	1 Qntl.	30.732	33.006168	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	406.21	85.3041	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	16.1466671	161.466671	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	186.25	39.1125	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9973.556711
Total GST (a)	117.53856
OVERHEAD CHARGES @ 7.5% (+)	756.832145325
CONTRACTOR PROFIT @ 7.5% (+)	813.59455622437
LABOUR CESS @ 1% (+)	116.61521972549
Grand Total	11778.137192275
Say For Unit 1 (Grand Total/10)	1177.8137192275

Item 3

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	608	836	150.48
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	66.85	10.0275	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	16.1466671	161.466671	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	406.21	60.9315	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	186.25	27.9375	0

Total Amount (a+b+c)	15116.119671
Total GST (a)	150.48
OVERHEAD CHARGES @ 7.5% (+)	1144.994975325
CONTRACTOR PROFIT @ 7.5% (+)	1230.8695984744
LABOUR CESS @ 1% (+)	176.42464244799
Grand Total	17818.888887247
Say For Unit 1 (Grand Total/10)	1781.8888887247

Item 4

Dismantling (AR1620): Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling and removing 2.5 cm thick grading concrete from roof

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.5	Per day	462	693	0
LR001 : Male mulia	0.75	Per day	462	346.5	0

Total Amount (a+b+c)

1039.5

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

77.9625

CONTRACTOR PROFIT @ 7.5% (+)

83.8096875

LABOUR CESS @ 1% (+)

12.012721875

Grand Total

1213.284909375

Say For Unit 1 (Grand Total/9.3)

130.46074294355

Item 5

Concrete (AR0318): 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)

Sub-Item of Work

4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1.008	Per day	462	465.696	0
LR044 : Mason	0.165	Per day	612	100.98	0
BRM340 : Cement	0.1287	1 Qntl.	608	78.2496	14.084928
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	66.85	1.2033	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	850.2	15.3036	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	1396.62	25.13916	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	30.732	3.9552084	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	406.21	7.31178	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	536.41	9.65538	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	536.41	9.65538	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	186.25	3.3525	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	439.5	7.911	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	439.5	7.911	0

Total Amount (a+b+c)	736.3239084
Total GST (a)	14.084928
OVERHEAD CHARGES @ 7.5% (+)	56.28066273
CONTRACTOR PROFIT @ 7.5% (+)	60.50171243475
LABOUR CESS @ 1% (+)	8.6719121156475
Grand Total	875.8631236804
Say For Unit 1 (Grand Total/1)	875.8631236804

Item 6

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0

Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.48567	0.06070875	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.48567	0.043866967741935	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	159.17526120161
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.938144590121
CONTRACTOR PROFIT @ 7.5% (+)	12.83350543438
LABOUR CESS @ 1% (+)	1.8394691122611
Grand Total	185.78638033838
Say For Unit 1 (Grand Total/1)	185.78638033838

Item 7
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	608	1392.32	250.6176
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.85	32.088	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
--------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	536.41	514.9536	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	186.25	89.4	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	439.5	421.92	0

Total Amount (a+b+c)	5574.43868				
Total GST (a)	250.6176				
OVERHEAD CHARGES @ 7.5% (+)	436.879221				
CONTRACTOR PROFIT @ 7.5% (+)	469.645162575				
LABOUR CESS @ 1% (+)	67.31580663575				
Grand Total	6798.8964702107				
Say For Unit 1 (Grand Total/1)	6798.8964702107				

Item 8

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6176.71	3137.76868	564.7983624
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	36.677	18.631916	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7364.900596				
Total GST (a)	564.7983624				
OVERHEAD CHARGES @ 7.5% (+)	594.72742188				
CONTRACTOR PROFIT @ 7.5% (+)	639.331978521				
LABOUR CESS @ 1% (+)	91.63758358801				
Grand Total	9255.395942389				
Say For Unit 1 (Grand Total/0.508)	18219.283351159				

Item 9

Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	608	21.7664	3.917952
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	66.85	1.00275	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	406.21	6.09315	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	186.25	2.79375	0

Total Amount (a+b+c)	166.8762556
Total GST (a)	3.917952
OVERHEAD CHARGES @ 7.5% (+)	12.80956557
CONTRACTOR PROFIT @ 7.5% (+)	13.77028298775
LABOUR CESS @ 1% (+)	1.9737405615775
Grand Total	199.34779671933
Say For Unit 1 (Grand Total/1)	199.34779671933

LAXMAN KUMAR MURMU
JE
Bahalda Block

MADAN MOHAN NAIK
AEE
Bahalda Block

MayurbhanjBahaldaBDO
BDO
Bahalda Block