

Analysis

**OD/354/3380/117913/411564/00101988 : Repair and Maintenance of High School SRK Nodal
High School, Kendubadi
Block : Polosara, Gram Panchayat : Kendubadi
Created By:SASI BHUSAN MAHAPATRO**

Item 1

Painting (AR0901di): Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	159.03	133.5852	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0.30732	0.2581488	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0	0	0

Total Amount (a+b+c)	670.8433488
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	50.31325116
CONTRACTOR PROFIT @ 7.5% (+)	54.086744997
LABOUR CESS @ 1% (+)	7.75243344957
Grand Total	782.99577840657
Say For Unit 1 (Grand Total/9.3)	84.193094452319

Item 2

Painting (AR0920k): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)

Sub-Item of Work
Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.5508	Per day	612	337.0896	0
LR001 : Male mulia	0.6528	Per day	462	301.5936	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.30732	0.38415	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)				950.74235	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				71.30567625	
CONTRACTOR PROFIT @ 7.5% (+)				76.65360196875	
LABOUR CESS @ 1% (+)				10.987016282188	
Grand Total				1109.6886445009	
Say For Unit 1 (Grand Total/10)				110.96886445009	

Item 3

Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work
Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.30732	0.3572595	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.2650095				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	113.4198757125				
CONTRACTOR PROFIT @ 7.5% (+)	121.92636639094				
LABOUR CESS @ 1% (+)	17.476112516034				
Grand Total	1765.0873641195				
Say For Unit 1 (Grand Total/9.3)	189.7943402279				

Item 4

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	560.45	601.9233	108.346194
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	66.23	13.9083	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	30.732	2.335632	0
BRM340 : Cement	1.074	1 Qntl.	30.732	33.006168	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	341.11	71.6331	0

BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
--	----	-----------	------------	------------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	40.25	8.4525	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9827.579681
Total GST (a)	108.346194
OVERHEAD CHARGES @ 7.5% (+)	745.194440625
CONTRACTOR PROFIT @ 7.5% (+)	801.08402367187
LABOUR CESS @ 1% (+)	114.82204339297
Grand Total	11597.02638269
Say For Unit 1 (Grand Total/10)	1159.702638269

Item 5

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0

BRM340 : Cement	1.375	1 Qntl.	560.45	770.61875	138.711375
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	66.23	9.9345	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	40.25	6.0375	0

Total Amount (a+b+c)	14969.888751
Total GST (a)	138.711375
OVERHEAD CHARGES @ 7.5% (+)	1133.14500945
CONTRACTOR PROFIT @ 7.5% (+)	1218.1308851587
LABOUR CESS @ 1% (+)	174.59876020609
Grand Total	17634.474780815
Say For Unit 1 (Grand Total/10)	1763.4474780815

Sarat Kumar Malla
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block