

Analysis

**OD/362/3458/275270/408425/00102761 : Construction of protection wall at Gateshwarpur
Sana Pokhari at Sahaspur
Block : Banapur, Gram Panchayat : Bhabanipur
Created By:Sri Bikash Kumar Mohanty**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	1321.91	132191	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	43.25	4325	0

Total Amount (a+b+c)	147845.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	11088.399				
CONTRACTOR PROFIT @ 7.5% (+)	11920.028925				
LABOUR CESS @ 1% (+)	1708.53747925				
Grand Total	172562.28540425				
Say For Unit 1 (Grand Total/100)	1725.6228540425				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	544.6	1247.134	224.48412
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.58	30.0384	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	1321.91	634.5168	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	907.91	871.5936	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	43.25	20.76	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	195.5	187.68	0

Total Amount (a+b+c)	5906.88503
Total GST (a)	224.48412
OVERHEAD CHARGES @ 7.5% (+)	459.85268625
CONTRACTOR PROFIT @ 7.5% (+)	494.34163771875
LABOUR CESS @ 1% (+)	70.855634739688
Grand Total	7156.4191087084
Say For Unit 1 (Grand Total/1)	7156.4191087084

Item 4

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	544.6	1891.55918	340.4806524
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.58	28.161	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1397.67	503.1612	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0

LR027 : Carpenter	0.25	Per day	562	140.5	0
-------------------	------	---------	-----	-------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	1321.91	594.8595	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	907.91	326.8476	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	907.91	490.2714	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	43.25	19.4625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	195.5	70.38	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	195.5	105.57	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	7006.61363392
Total GST (a)	340.4806524
OVERHEAD CHARGES @ 7.5% (+)	551.032071474
CONTRACTOR PROFIT @ 7.5% (+)	592.35947683455
LABOUR CESS @ 1% (+)	84.904858346285
Grand Total	8575.3906929748
Say For Unit 1 (Grand Total/1)	8575.3906929748

Item 5

Masonry Stone Work (AR0717): Laterite stone masonry in cement mortar (1:6) in foundation and plinth cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.

Sub-Item of Work
Laterite stone masonry

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	544.6	311.5112	56.072016
LR001 : Male mulia	1.21	Per day	462	559.02	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.175	Per day	612	107.1	0
LR008 : Sangi mulia	1.41	Per day	512	721.92	0
LR052 : Stone dresser/ Cutter	2.12	Per day	612	1297.44	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	62.58	15.0192	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	729.98	729.98	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	24.787	14.178164	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	1321.91	317.2584	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	731.71	731.71	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	43.25	10.38	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	190.25	190.25	0

Total Amount (a+b+c)	5595.866964
Total GST (a)	56.072016
OVERHEAD CHARGES @ 7.5% (+)	423.8954235
CONTRACTOR PROFIT @ 7.5% (+)	455.6875802625
LABOUR CESS @ 1% (+)	65.315219837625
Grand Total	6596.8372036001
Say For Unit 1 (Grand Total/1)	6596.8372036001

Item 6
R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.
Sub-Item of Work Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6374	66927	12046.86

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)					73665.3435
Total GST (a)					12046.86
OVERHEAD CHARGES @ 7.5% (+)					6428.4152625
CONTRACTOR PROFIT @ 7.5% (+)					6910.5464071875
LABOUR CESS @ 1% (+)					990.51165169688
Grand Total					100041.67682138
Say For Unit 1 (Grand Total/10)					10004.167682138

Item 7

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	544.6	365.9712	65.874816

BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	62.58	17.5224	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	1321.91	370.1348	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0.8641	302.435	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	43.25	12.11	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5056.542764
Total GST (a)	65.874816
OVERHEAD CHARGES @ 7.5% (+)	384.1813185
CONTRACTOR PROFIT @ 7.5% (+)	412.9949173875
LABOUR CESS @ 1% (+)	59.195938158875
Grand Total	5978.7897540464
Say For Unit 1 (Grand Total/1)	5978.7897540464

Item 8

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	544.6	19.49668	3.5094024
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	62.58	0.9387	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	1321.91	19.82865	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	43.25	0.64875	0

Total Amount (a+b+c)	175.9201546				
Total GST (a)	3.5094024				
OVERHEAD CHARGES @ 7.5% (+)	13.457216775				
CONTRACTOR PROFIT @ 7.5% (+)	14.466508033125				
LABOUR CESS @ 1% (+)	2.0735328180813				
Grand Total	209.42681462621				
Say For Unit 1 (Grand Total/1)	209.42681462621				

snigdharani jena
JE
Banapur Block

SURESH MALIK
AEE
Banapur Block

Sri Bikash Kumar Mohanty
BDO
Banapur Block