

Analysis

**OD/345/3291/115900/419930/00104742 : CONSTRUCTION OF CULTURAL CENTRE AT
MADHYAM PADA BURDA
Block : Loisinga, Gram Panchayat : Burda
Created By:AKHAYA PANI UDDU**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	50.25	5025	0

Total Amount (a+b+c)	52040.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	3903.024
CONTRACTOR PROFIT @ 7.5% (+)	4195.7508
LABOUR CESS @ 1% (+)	601.390948
Grand Total	60740.485748
Say For Unit 1 (Grand Total/100)	607.40485748

Item 2
Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	504.18	1628.5014	293.130252
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	159.5	143.55	0

Total Amount (a+b+c)	6134.13841
Total GST (a)	293.130252
OVERHEAD CHARGES @ 7.5% (+)	482.04514965
CONTRACTOR PROFIT @ 7.5% (+)	518.19853587375
LABOUR CESS @ 1% (+)	74.275123475237
Grand Total	7501.787470999
Say For Unit 1 (Grand Total/1)	7501.787470999

Item 3

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	504.18	338.80896	60.9856128
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0	0	0

Total Amount (a+b+c)

4812.258024

Total GST (a)

60.9856128

OVERHEAD CHARGES @ 7.5% (+)

365.49327276

CONTRACTOR PROFIT @ 7.5% (+)

392.905268217

LABOUR CESS @ 1% (+)

56.3164217777

Grand Total

5687.9585995548

Say For Unit 1 (Grand Total/1)

5687.9585995548

Item 4

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)	23839.2
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1787.94
CONTRACTOR PROFIT @ 7.5% (+)	1922.0355
LABOUR CESS @ 1% (+)	275.491755
Grand Total	27824.667255
Say For Unit 1 (Grand Total/100)	278.24667255

Item 5

Painting (AR0918hk): Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).

Sub-Item of Work

Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918fk)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.06528	Per day	462	30.15936	0
LR048 : Painter/ Polisher	0.05508	Per day	612	33.70896	0
Combine :: Painting (AR0901dik)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.054838709677419	Per day	612	33.561290322581	0
LR001 : Male mulia	0.054838709677419	Per day	462	25.335483870968	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.24787	0.03098375	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.24787	0.022388258064516	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	161.53121620161
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	12.114841215121
CONTRACTOR PROFIT @ 7.5% (+)	13.023454306255
LABOUR CESS @ 1% (+)	1.8666951172299
Grand Total	188.53620684022
Say For Unit 1 (Grand Total/1)	188.53620684022

Item 6

Iron Work (AR1703): Iron work wrought and put up in trusses and record racks including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.

Sub-Item of Work

Iron work wrought and put up in trusses and record racks

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6175.4	3137.1032	564.678576
LR001 : Male mulia	2.5	Per day	462	1155	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR026 : Black smith	1.25	Per day	562	702.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	42.622	21.651976	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	6090.255176
Total GST (a)	564.678576
OVERHEAD CHARGES @ 7.5% (+)	499.1200314
CONTRACTOR PROFIT @ 7.5% (+)	536.554033755
LABOUR CESS @ 1% (+)	76.90607817155
Grand Total	7767.5138953265
Say For Unit 1 (Grand Total/0.508)	15290.381683714

Item 7

Roofing (AR1132): Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge

Sub-Item of Work

Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM149 : G.C.I. Sheet 0.30mm thick	9.3	1 Sqm	317.5	2952.75	0
LR001 : Male mulia	2	Per day	462	924	0
LR047 : Fitter	1	Per day	612	612	0
LR045 : Carpenter	0.5	Per day	612	306	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM149 : G.C.I. Sheet 0.30mm thick	9.3	1 Sqm	1.108172	10.3059996	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM149 : G.C.I. Sheet 0.30mm thick	9.3	1 Sqm	0	0	0

Total Amount (a+b+c)	4805.0559996
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	360.37919997
CONTRACTOR PROFIT @ 7.5% (+)	387.40763996775
LABOUR CESS @ 1% (+)	55.528428395377
Grand Total	5608.3712679331
Say For Unit 1 (Grand Total/9.3)	603.0506739713

Item 8

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	504.18	1154.5722	207.822996
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	50.25	24.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	159.5	153.12	0

Total Amount (a+b+c)	4775.07523
Total GST (a)	207.822996
OVERHEAD CHARGES @ 7.5% (+)	373.71736695
CONTRACTOR PROFIT @ 7.5% (+)	401.74616947125
LABOUR CESS @ 1% (+)	57.583617624213
Grand Total	5815.9453800455
Say For Unit 1 (Grand Total/1)	5815.9453800455

Item 9

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	504.18	1379.94066	248.3893188
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	9.6011111	96.011111	0
BRM340 : Cement	2.737	1 Qntl.	24.787	67.842019	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	341.11	44.3443	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	50.25	6.5325	0

Total Amount (a+b+c)

11326.30499

Total GST (a)

248.3893188

OVERHEAD CHARGES @ 7.5% (+)

868.10207316

CONTRACTOR PROFIT @ 7.5% (+)

933.209728647

LABOUR CESS @ 1% (+)

133.76006110607

Grand Total	13509.766171713
Say For Unit 1 (Grand Total/10)	1350.9766171713

Kedarnath Meher
JE
Loisinga Block

Sidhartha Padhi
AEE
Loisinga Block

AKHAYA PANI UDDU
BDO
Loisinga Block