

Analysis

**OD/362/3458/119576/408501/00105229 : Development of play ground at Pratap
Block : Banapur, Gram Panchayat : Tumuraput
Created By:Sri Bikash Kumar Mohanty**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0122Bii): Earthwork in hard soil or gravelly soil within 5 Km.mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.
Sub-Item of Work Earthwork in hard soil or gravelly soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMM402 : Loading into trucks and unloading from trucks within 50 Meter lead (2/3 of rate is consider for loading).	-0.6666	1 Cum	175.38	116.908308	0
BRMM401 : Conveyance of material by 10 ton trucks within 5 KM including loading and unloading	1	1 Cum	276.01	276.01	0
LR002 : Female mulia	0.215	Per day	462	99.33	0
LR001 : Male mulia	0.215	Per day	462	99.33	0

Total Amount (a+b+c)	357.761692
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	26.8321269
CONTRACTOR PROFIT @ 7.5% (+)	28.8445364175
LABOUR CESS @ 1% (+)	4.134383553175
Grand Total	417.57273887067
Say For Unit 1 (Grand Total/1)	417.57273887067

Item 3

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	1321.91	132191	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	43.25	4325	0

Total Amount (a+b+c)	147845.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11088.399
CONTRACTOR PROFIT @ 7.5% (+)	11920.028925
LABOUR CESS @ 1% (+)	1708.53747925
Grand Total	172562.28540425
Say For Unit 1 (Grand Total/100)	1725.6228540425

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work
Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	544.6	365.9712	65.874816
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	62.58	17.5224	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	128.792	86.548224	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	1321.91	370.1348	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	2.307825	807.73875	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	43.25	12.11	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5631.737874
Total GST (a)	65.874816
OVERHEAD CHARGES @ 7.5% (+)	427.32095175
CONTRACTOR PROFIT @ 7.5% (+)	459.37002313125
LABOUR CESS @ 1% (+)	65.843036648812
Grand Total	6650.1467015301
Say For Unit 1 (Grand Total/1)	6650.1467015301

Item 5

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	544.6	1247.134	224.48412
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.58	30.0384	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	128.792	294.93368	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	1321.91	634.5168	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	907.91	871.5936	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	43.25	20.76	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	170.5	163.68	0

Total Amount (a+b+c)	6121.05648
Total GST (a)	224.48412
OVERHEAD CHARGES @ 7.5% (+)	475.915545
CONTRACTOR PROFIT @ 7.5% (+)	511.609210875
LABOUR CESS @ 1% (+)	73.33065355875
Grand Total	7406.3960094338
Say For Unit 1 (Grand Total/1)	7406.3960094338

Item 6

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
LR002 : Female mulia	1.4	Per day	462	646.8	0	
LR001 : Male mulia	3.2	Per day	462	1478.4	0	
LR025 : Mason	0.68	Per day	562	382.16	0	
BRM340 : Cement	3.23	1 Qntl.	544.6	1759.058	316.63044	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.58	28.161	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1372.71	1235.439	0	

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	1321.91	594.8595	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	907.91	817.119	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	43.25	19.4625	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	170.5	153.45	0	

Total Amount (a+b+c)	7194.97101					
Total GST (a)	316.63044					
OVERHEAD CHARGES @ 7.5% (+)	563.37010875					
CONTRACTOR PROFIT @ 7.5% (+)	605.62286690625					
LABOUR CESS @ 1% (+)	86.805944256562					
Grand Total	8767.4003699128					
Say For Unit 1 (Grand Total/1)	8767.4003699128					

MANIKA BEHERA
JE
Banapur Block

SURESH MALIK
AEE
Banapur Block

Sri Bikash Kumar Mohanty
BDO
Banapur Block