

## Analysis

OD/346/3305/116234/393276/00068433 : Const. of boundary wall of bayarsahi primary school

Block : Nilgiri, Gram Panchayat : Bhaunriabad

Created By: Bikram Kishore Parida

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

**Total Amount (a+b+c)**

23839.2

**Total GST (a)**

0

**OVERHEAD CHARGES @ 7.5% (+)**

1787.94

**CONTRACTOR PROFIT @ 7.5% (+)**

1922.0355

**LABOUR CESS @ 1% (+)**

275.491755

**Grand Total**

27824.667255

**Say For Unit 1 (Grand Total/100)**

278.24667255

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	471.31	47131	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

<b>Total Amount (a+b+c)</b>	104260.32				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	7819.524				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	8405.9883				
<b>LABOUR CESS @ 1% (+)</b>	1204.858323				
<b>Grand Total</b>	121690.690623				
<b>Say For Unit 1 (Grand Total/100)</b>	1216.90690623				

<b>Item 3</b>
<b>Concrete (AR0303a):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	2.5	Per day	462	1155	0
<b>LR025</b> : Mason	0.18	Per day	562	101.16	0
<b>BRM340</b> : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	30.732	70.37628	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	471.31	226.2288	0
<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	953.91	915.7536	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	522.5	501.6	0

<b>Total Amount (a+b+c)</b>	5871.57388
<b>Total GST (a)</b>	224.929296
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	457.2377382
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	491.530568565
<b>LABOUR CESS @ 1% (+)</b>	70.45271482765
<b>Grand Total</b>	7115.7241975927
<b>Say For Unit 1 (Grand Total/1)</b>	7115.7241975927

#### Item 4

**R.C.C. Work (AR0404Aa):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	545.68	1895.310344	341.15586192
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0

<b>LR008</b> : Sangi mulia	0.075	Per day	512	38.4	0
<b>LR027</b> : Carpenter	0.075	Per day	562	42.15	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	953.91	343.4076	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	953.91	515.1114	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	245.856	0.98465328	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	245.856	0.226433376	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	522.5	188.1	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	522.5	282.15	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	6428.394010206
<b>Total GST (a)</b>	341.15586192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	507.71624040945
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	545.79495844016
<b>LABOUR CESS @ 1% (+)</b>	78.230610709756
<b>Grand Total</b>	7901.2916816854
<b>Say For Unit 1 (Grand Total/1)</b>	7901.2916816854

**Item 5**

**R.C.C. Work (AR0404Ac):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	545.68	1895.310344	341.15586192
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410d)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
<b>LR008</b> : Sangi mulia	5.23875	Per day	512	2682.24	0
<b>LR027</b> : Carpenter	5.23875	Per day	562	2944.1775	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	953.91	343.4076	0

<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	953.91	515.1114	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	245.856	11.146865184	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	245.856	10.210153824	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	522.5	188.1	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	522.5	282.15	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	14408.284624518
<b>Total GST (a)</b>	341.15586192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1106.2080364829
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1189.1736392191
<b>LABOUR CESS @ 1% (+)</b>	170.4482216214
<b>Grand Total</b>	17215.270383761
<b>Say For Unit 1 (Grand Total/1)</b>	17215.270383761

**Item 6**

**R.C.C. Work (AR0409):** Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

**Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR001</b> : Male mulia	8	Per day	462	3696	0
<b>LR046</b> : Blacksmith	3	Per day	612	1836	0
<b>LR010</b> : Mate	0.44	Per day	512	225.28	0
<b>BRM162</b> : Binding Wire.	8	1 Kg.	90	720	0
<b>BRM341</b> : Steel	10.5	1 Qntl.	6354.22	66719.31	12009.4758

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

<b>Total Amount (a+b+c)</b>	73519.276				
<b>Total GST (a)</b>	12009.4758				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	6414.656385				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	6895.755613875				
<b>LABOUR CESS @ 1% (+)</b>	988.39163798875				
<b>Grand Total</b>	99827.555436864				
<b>Say For Unit 1 (Grand Total/10)</b>	9982.7555436864				

### Item 7

**Masonry Brick Work (AR0603bi):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure**

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	545.68	366.69696	66.0054528
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	30.732	20.651904	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	471.31	131.9668	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.7476	611.66	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1000 Nos	0	0	0

<b>Total Amount (a+b+c)</b>	5281.044564				
<b>Total GST (a)</b>	66.0054528				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	401.02875126				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	431.1059076045				
<b>LABOUR CESS @ 1% (+)</b>	61.791846756645				
<b>Grand Total</b>	6240.9765224211				
<b>Say For Unit 1 (Grand Total/1)</b>	6240.9765224211				

**Item 8**

**Plastering (AR1004):** 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work  
**12mm thick cement plaster (1:6) over Brick work in inside**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.05	Per day	462	23.1	0
<b>LR001</b> : Male mulia	0.07	Per day	462	32.34	0
<b>LR025</b> : Mason	0.14	Per day	562	78.68	0
<b>BRM340</b> : Cement	0.0358	1 Qntl.	545.68	19.535344	3.51636192
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	471.31	7.06965	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0358	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

<b>Total Amount (a+b+c)</b>	169.6121496
<b>Total GST (a)</b>	3.51636192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	12.984638364
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	13.9584862413
<b>LABOUR CESS @ 1% (+)</b>	2.000716361253
<b>Grand Total</b>	202.07235248655
<b>Say For Unit 1 (Grand Total/1)</b>	202.07235248655

<b>Item 9</b>
<b>Plastering (AR1014):</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.
Sub-Item of Work <b>16mm thick cement Plaster in CM (1:6) over brick work in inside.</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.11	Per day	462	50.82	0
<b>LR001</b> : Male mulia	0.13	Per day	462	60.06	0
<b>LR025</b> : Mason	0.16	Per day	562	89.92	0
<b>BRM340</b> : Cement	0.043	1 Qntl.	545.68	23.46424	4.2235632
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.043	1 Qntl.	30.732	1.321476	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1 Cum	471.31	8.48358	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.043	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1 Cum	442.25	7.9605	0

<b>Total Amount (a+b+c)</b>	243.413636
<b>Total GST (a)</b>	4.2235632

<b>OVERHEAD CHARGES @ 7.5% (+)</b>	18.57278994
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	19.9657491855
<b>LABOUR CESS @ 1% (+)</b>	2.861757383255
<b>Grand Total</b>	289.03749570875
<b>Say For Unit 1 (Grand Total/1)</b>	289.03749570875

### Item 10

**Painting (AR0918cb):** Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

**Finishing wall two coats with weather coat with one coat waterbound Primer**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918f)</b>					
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	194.79	24.34875	0
<b>LR001 : Male mulia</b>	0.064	Per day	462	29.568	0
<b>LR048 : Painter/ Polisher</b>	0.054	Per day	612	33.048	0
<b>Combine :: Painting (AR0901di)</b>					
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	159.03	14.364	0
<b>LR048 : Painter/ Polisher</b>	0.053763440860215	Per day	612	32.903225806452	0
<b>LR001 : Male mulia</b>	0.053763440860215	Per day	462	24.838709677419	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	0.30732	0.038415	0
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	0.30732	0.027757935483871	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	0	0	0
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	159.13685841935
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	11.935264381452
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	12.83040921006
<b>LABOUR CESS @ 1% (+)</b>	1.8390253201087
<b>Grand Total</b>	185.74155733098

Say For Unit 1 (Grand Total/1)

185.74155733098

**Ramesh Singh**  
**JE**  
**Nilgiri Block**

**Sarat kumar Upadhyay**  
**AEE**  
**Nilgiri Block**

**Bikram Kishore Parida**  
**BDO**  
**Nilgiri Block**