

Analysis

OD/358/3418/118792/422863/00102476 : DEVELOPMENT OF PLAY FIELD AT KUTELPADAR
Block : Lanjigarh, Gram Panchayat : Bhurtigarh
Created By:SRI SASANK PATRA

Item 1

miscellaneous (ARM306): Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) requiring blasting in canal, foundation of structures and other deep cutting sections in dry, wet or submerged conditions by mechanical drilling and appropriate blasting & disposal of excavated materials with 1 Km lead, loading into and transportation by transport vehicle and depositing the excavated materials neatly in approved specified dump yard within 1 Km lead & dressing to pro section as direction by the Engineer-in-charge and trimming of bed and slope to the design finished section manually, if necessary including all cost of drilling conveyance and storage of explosive, fuse coil, detonators, all accessories, machine charges etc. complete as specification and direction of the Engineer-in-charge. (Special Items for Irrigation works).

Sub-Item of Work

Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) requiring blasting in canal,

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM306 : Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) requiring blasting in canal, foundation of structures and other deep cutting sections in dry, wet or submerged conditions by mechanical drilling and appropriate blasting & disposal of excavated materials with 1 Km lead, loading into and transportation by transport vehicle and depositing the excavated materials neatly in approved specified dump yard within 1 Km lead & dressing to pro section as direction by the Engineer-in-charge and trimming of bed and slope to the design finished section manually, if necessary including all cost of drilling conveyance and storage of explosive, fuse coil, detonators, all accessories, machine charges etc. complete as specification and direction of the Engineer-in-charge. (Special Items for Irrigation works)	1	1 Cum	308.4	308.4	0

Total Amount (a+b+c)

308.4

Total GST (a)

0

Grand Total

0

Say For Unit 1 (Grand Total/1)

0

Item 2

Road Work (AR1307): Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.

Sub-Item of Work

Supplying & spreading moorum and consolidation with HRR

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

