

Analysis

OD/346/3299/275532/392811/00115267 : Construction of CC Road Bangra AWC Center to Kurukura AWC Center
Block : Baleshwar, Gram Panchayat : Khannagar
Created By:Uttam Kumar Jena

Item 1
Earth Work (AR0101a1): Earthwork in ordinary soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.
Sub-Item of Work Earthwork in ordinary soil within 50m to 75m lead and 1.5m, initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Earth Work (AR0101a)					
LR002 : Female mulia	16	Per day	462	7392	0
LR001 : Male mulia	16	Per day	462	7392	0
Combine :: Earth Work (AR0107)					
LR001 : Male mulia	3	Per day	462	1386	0

Total Amount (a+b+c)	16170
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1212.75
CONTRACTOR PROFIT @ 7.5% (+)	1303.70625
LABOUR CESS @ 1% (+)	186.8645625
Grand Total	18873.3208125
Say For Unit 1 (Grand Total/100)	188.733208125

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	523.39	52339	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	427.25	42725	0

Total Amount (a+b+c)	107968.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	8097.624				
CONTRACTOR PROFIT @ 7.5% (+)	8704.9458				
LABOUR CESS @ 1% (+)	1247.708898				
Grand Total	126018.598698				
Say For Unit 1 (Grand Total/100)	1260.18598698				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	523.39	251.2272	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1165.51	1118.8896	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	427.25	205.08	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	522.5	501.6	0

Total Amount (a+b+c)	6292.08268
Total GST (a)	224.929296
OVERHEAD CHARGES @ 7.5% (+)	488.7758982
CONTRACTOR PROFIT @ 7.5% (+)	525.434090565
LABOUR CESS @ 1% (+)	75.31221964765
Grand Total	7606.5341844127
Say For Unit 1 (Grand Total/1)	7606.5341844127

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	545.68	1762.5464	317.258352
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	523.39	235.5255	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1165.51	1048.959	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	427.25	192.2625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	522.5	470.25	0

Total Amount (a+b+c)	7607.72176
Total GST (a)	317.258352
OVERHEAD CHARGES @ 7.5% (+)	594.3735084
CONTRACTOR PROFIT @ 7.5% (+)	638.95152153
LABOUR CESS @ 1% (+)	91.5830514193
Grand Total	9249.8881933493
Say For Unit 1 (Grand Total/1)	9249.8881933493

Item 5
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0
Total Amount (a+b+c)	2142.50140404				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	160.687605303				
CONTRACTOR PROFIT @ 7.5% (+)	172.73917570073				
LABOUR CESS @ 1% (+)	24.759281850437				
Grand Total	2500.6874668942				
Say For Unit 1 (Grand Total/10)	250.06874668942				

K S ROSALIN
JE
Baleshwar Block

PURUSOTTAM KARAN
AEE
Baleshwar Block

Uttam Kumar Jena
BDO
Baleshwar Block