

Analysis

**OD/354/3382/117950/412613/00116066 : MAINTENANCE AND IMPROVEMENT OF ROAD
INFRASTRUCTURE FROM MAIN ROAD TO AWC-II
Block : Rangeilunda, Gram Panchayat : Badakusasthali
Created By: BISWAJIT RAY**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)	23839.2
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1787.94
CONTRACTOR PROFIT @ 7.5% (+)	1922.0355
LABOUR CESS @ 1% (+)	275.491755
Grand Total	27824.667255
Say For Unit 1 (Grand Total/100)	278.24667255

Item 2

Earth Work (AR0115a): Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with crusher dust well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	100	1 Cum	113.39	11339	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	100	1 Cum	406.21	40621	0
--	-----	----------	--------	-------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	100	1 Cum	110.25	11025	0

Total Amount (a+b+c)	68695.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	5152.149				
CONTRACTOR PROFIT @ 7.5% (+)	5538.560175				
LABOUR CESS @ 1% (+)	793.86029175				
Grand Total	80179.88946675				
Say For Unit 1 (Grand Total/100)	801.7988946675				

Item 3

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	560.45	1810.2535	325.84563
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.23	29.8035	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	666.61	299.9745	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0
--	-----	-----------	--------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	409.5	368.55	0

Total Amount (a+b+c)	6787.36536
Total GST (a)	325.84563
OVERHEAD CHARGES @ 7.5% (+)	533.49082425
CONTRACTOR PROFIT @ 7.5% (+)	573.50263606875
LABOUR CESS @ 1% (+)	82.202044503187
Grand Total	8302.4064948219
Say For Unit 1 (Grand Total/1)	8302.4064948219

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2142.50140404
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.687605303
CONTRACTOR PROFIT @ 7.5% (+)	172.73917570073
LABOUR CESS @ 1% (+)	24.759281850437
Grand Total	2500.6874668942
Say For Unit 1 (Grand Total/10)	250.06874668942

Item 5
miscellaneous (ARM287): Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.
Sub-Item of Work Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	62.86	1.8858	0
BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	608.4	608.4	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	666.61	19.9983	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	110.25	3.3075	0

Total Amount (a+b+c)	633.5916
Total GST (a)	0
Grand Total	0

PRATAP KUMAR NAYAK
JE
Rangeilunda Block

SRI NABIN BHUYAN
AEE
Rangeilunda Block

BISWAJIT RAY
BDO
Rangeilunda Block