

Analysis

**OD/361/3452/119466/385974/00102175 : Construction of Protection Wall at Thakurani
Andhari Sala, Palaspanga GP
Block : Kendujhar Sadar, Gram Panchayat : Palaspanga
Created By:Binod Chandra Panda**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	55	5500	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	898.71	89871	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	50.25	5025	0

Total Amount (a+b+c)	106106.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	7957.974				
CONTRACTOR PROFIT @ 7.5% (+)	8554.82205				
LABOUR CESS @ 1% (+)	1226.1911605				
Grand Total	123845.3072105				
Say For Unit 1 (Grand Total/100)	1238.453072105				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	554.16	1269.0264	228.424752
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	65	31.2	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	28.354	64.93066	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	898.71	431.3808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	692.65	664.944	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	50.25	24.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	424.5	407.52	0

Total Amount (a+b+c)	5751.52186
Total GST (a)	228.424752
OVERHEAD CHARGES @ 7.5% (+)	448.4959959
CONTRACTOR PROFIT @ 7.5% (+)	482.1331955925
LABOUR CESS @ 1% (+)	69.105758034925
Grand Total	6979.6815615274
Say For Unit 1 (Grand Total/1)	6979.6815615274

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.16	372.39552	67.0311936
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	28.354	19.053888	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	898.71	251.6388	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0

BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

Total Amount (a+b+c)	5001.043208
Total GST (a)	67.0311936
OVERHEAD CHARGES @ 7.5% (+)	380.10558012
CONTRACTOR PROFIT @ 7.5% (+)	408.613498629
LABOUR CESS @ 1% (+)	58.56793480349
Grand Total	5915.3614151525
Say For Unit 1 (Grand Total/1)	5915.3614151525

Item 5

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.16	372.39552	67.0311936
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	28.354	19.053888	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	898.71	251.6388	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5034.043208
Total GST (a)	67.0311936
OVERHEAD CHARGES @ 7.5% (+)	382.58058012
CONTRACTOR PROFIT @ 7.5% (+)	411.274123629
LABOUR CESS @ 1% (+)	58.94929105349
Grand Total	5953.8783964025
Say For Unit 1 (Grand Total/1)	5953.8783964025

Item 6

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	28.354	98.4819482	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	898.71	404.4195	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	692.65	249.354	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	692.65	374.031	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6111.067206246
Total GST (a)	346.45750704
OVERHEAD CHARGES @ 7.5% (+)	484.31435349645
CONTRACTOR PROFIT @ 7.5% (+)	520.63793000868
LABOUR CESS @ 1% (+)	74.624769967911

Grand Total	7537.101766759
Say For Unit 1 (Grand Total/1)	7537.101766759

Item 7

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	28.354	98.4819482	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	898.71	404.4195	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	562.45	202.482	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	562.45	303.723	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6743.21604302
Total GST (a)	346.45750704
OVERHEAD CHARGES @ 7.5% (+)	531.7255162545
CONTRACTOR PROFIT @ 7.5% (+)	571.60492997359
LABOUR CESS @ 1% (+)	81.930039962881
Grand Total	8274.934036251
Say For Unit 1 (Grand Total/1)	8274.934036251

Item 8

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0

LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6841.58	71836.59	12930.5862

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	50.945	534.9225	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	78849.5925
Total GST (a)	12930.5862
OVERHEAD CHARGES @ 7.5% (+)	6883.5134025
CONTRACTOR PROFIT @ 7.5% (+)	7399.7769076875
LABOUR CESS @ 1% (+)	1060.6346901019
Grand Total	107124.10370029
Say For Unit 1 (Grand Total/10)	10712.410370029

Item 9

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	554.16	23.82888	4.2891984
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	65	1.17	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	28.354	1.219222	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	898.71	16.17678	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	50.25	0.9045	0

Total Amount (a+b+c)	244.099382				
Total GST (a)	4.2891984				
OVERHEAD CHARGES @ 7.5% (+)	18.62914353				
CONTRACTOR PROFIT @ 7.5% (+)	20.02632929475				
LABOUR CESS @ 1% (+)	2.8704405322475				
Grand Total	289.914493757				
Say For Unit 1 (Grand Total/1)	289.914493757				

Item 10

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	554.16	19.838928	3.57100704
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	65	0.975	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	28.354	1.0150732	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	898.71	13.48065	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	50.25	0.75375	0

Total Amount (a+b+c)	170.1834012				
Total GST (a)	3.57100704				
OVERHEAD CHARGES @ 7.5% (+)	13.031580618				

CONTRACTOR PROFIT @ 7.5% (+)	14.00894916435
LABOUR CESS @ 1% (+)	2.0079493802235
Grand Total	202.80288740257
Say For Unit 1 (Grand Total/1)	202.80288740257

Item 11

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6841.58	3475.52264	625.5940752
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	50.945	25.88006	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7709.9027
Total GST (a)	625.5940752
OVERHEAD CHARGES @ 7.5% (+)	625.16225814
CONTRACTOR PROFIT @ 7.5% (+)	672.0494275005
LABOUR CESS @ 1% (+)	96.327084608405
Grand Total	9729.0355454489
Say For Unit 1 (Grand Total/0.508)	19151.644774506

Item 12

Painting (AR0903): Painting two coats of enamel paint in inner surface paint including all costs of labour, Paint, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)

Sub-Item of Work

Painting two coats of enamel paint in inner surface paint (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.50945	0.592235625	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)

1512.499985625

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

113.43749892188

CONTRACTOR PROFIT @ 7.5% (+)

121.94531134102

LABOUR CESS @ 1% (+)

17.478827958879

Grand Total

1765.3616238468

Say For Unit 1 (Grand Total/9.3)

189.82383052116

Item 13

Painting (AR0901a): Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat in inner surface with primer of approved quality over woodwork

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM138 : Wood Primer	0.6975	1 Litre	155.08	108.1683	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM138 : Wood Primer	0.6975	1 Litre	0.50945	0.355341375	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM138 : Wood Primer	0.6975	1 Litre	0	0	0

Total Amount (a+b+c)	645.523641375				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	48.414273103125				
CONTRACTOR PROFIT @ 7.5% (+)	52.045343585859				
LABOUR CESS @ 1% (+)	7.4598325806398				
Grand Total	753.44309064462				
Say For Unit 1 (Grand Total/9.3)	81.01538609082				

Item 14

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	28.354	98.4819482	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	898.71	404.4195	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	692.65	249.354	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	692.65	374.031	0	
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0	
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0	

Total Amount (a+b+c)	14087.060659038
Total GST (a)	346.45750704
OVERHEAD CHARGES @ 7.5% (+)	1082.5138624559
CONTRACTOR PROFIT @ 7.5% (+)	1163.70240214
LABOUR CESS @ 1% (+)	166.79734430674

Grand Total	16846.531774981
Say For Unit 1 (Grand Total/1)	16846.531774981

Item 15

Painting (AR0918f): Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)

Sub-Item of Work

Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	194.79	243.4875	0
LR001 : Male mulia	0.64	Per day	462	295.68	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0.50945	0.6368125	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0	0	0

Total Amount (a+b+c)	870.2843125
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	65.2713234375
CONTRACTOR PROFIT @ 7.5% (+)	70.166672695312
LABOUR CESS @ 1% (+)	10.057223086328
Grand Total	1015.7795317191
Say For Unit 1 (Grand Total/10)	101.57795317191

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block