

TAX INVOICE

CREDIT

Name of the Dealers : SYAG Electricals & Construction
Address : Main Road, Sana Bazar, Ganjam, 761026
GSTIN : 21AFCPD7207A1Z1

Sl. No. : 162
Date : 27-03-2026
Order No. :
Date :

Name of the buyer : The Block Development Officer
Address : Panchayat Samit Tirtol,
Location : Near Trinath Mandap, Baisanilo, Garam GP
GSTIN : 21BBNB01034F3DR

Sl. No	NAME OF THE MATERIAL	UNIT	QTY	RATE	AMOUNT
1	Supply of 06 Meter GI Make Octagonal Pole Top-75mm, Bottom-100 mm, 3mm Thickness, the Base plate size-150mm X 150 mm X 12mm, Wind Speed 160 Km Hr (Make- utkarsh)	Nos	1	16420.00	16420.00
2	Supply of Two Side Arm for supporting and adjusting of Solar Light (GI Structure welded with top canopy at an angle of 90 degree suitable for the octagonal pole. The outer diameter of Arm of 40 mm MS Nut&bolts are to be provided on canopy to fix the Arm Rigidly on 6 mtr GI Tubular Pole	Nos	1	1480.00	1480.00
3	Supply of 30W Semi Integrated (All in two) Solar Street lights having 100Wp or more highly efficient Monocrystalline PV module with multipurpose arm & 12.8 X 42Ah or more lithium Ferritophosphate (LiFePO4) Battery (BIS Approved) which shall be inside the extruded aluminum luminaire housing (heat retardant type) MPPT charge controller having 92% efficiency & PIR Sensor. The initial lumen output of Semi Integrated street light shall be 4500 lumen or more in CCT 5000K to 5000K (lumen efficacy of 150lm/w as per LM79 report of third party NABL Lab (In house report of NABL accredited lab will not be acceptable). The LED Chip will be of OSRAM NISCHIA (CREE, SECOLE) Semiconductor only and should be with lenses for effective lighting distribution. The complete system & BMS should be designed to provide 3 days (36 Hrs) backup in dimming mode by activating PIR sensor and battery should be kept inside the luminaire and Monocrystalline panel (made in India) to be mounted on the top of the luminaire housing. The luminaire must be having IP66 protection for critical component like (LED Compartment, driver compartment & Battery). The Semi integrated street light is having 1k 08 Warranty on the Semi Integrated street lights must be 5 yrs. The following test reports, certifications must be submitted for the technical acceptance of the products: 1. LM 79 Report (third party NABL lab only) 2. IK 08 (report of Third Party NABL only) 3. IP 66 (report of third party NABL Lab only) 4. Panchayat Samit Tirtol, Baisanilo, Garam GP, Ganjam, Odisha	Nos	2	31680.00	63360.00
4	Construction of RCC foundation by using M20 grade RCC and Fe 415 grade reinforcement in the foundation by considering the SBC as 10 T per sq mtr and fixing the 4 nos fdn bolts in that foundation for installation of pole with solar light on that foundation. The work shall be executed as per the direction of Panchayat Samit Tirtol, Baisanilo, Garam GP, Ganjam, Odisha	Set	1	3470.00	3470.00
5	Erection and transportation of The Octagonal Tubular pole and Solar Light With the Help of Suitable Equipments excluding cost of material including cost of labour charges all wiring materials and labour	Nos	1	1315.00	1315.00
				Sub Total-	86045.00
				CGST 9% :-	7744.05
				SGST 9% :-	7744.05
				Grand Total	101533.10
				Or say	100000.00

BANK DETAILS

BANK NAME: STATE BANK OF INDIA
AC NO: 39174533952
IFSC CODE: SBIN0003816
BRANCH: GANJAM

Signature of the Dealer
For SYAG Electricals & Construction

