

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Baripada	Panchayat	Rajabasa
Work Code	OD/365/3490/120106/389175/00013481 (CONSTRUCTION OF CC ROAD GARBARDHANSOLE BHUTU CHHAKA TO BINDHANI HOUSE)						
Project Category	Road						
Financial Year	2023-24	Execution Level			Rajabasa, G.P		
Executing Agency	Panchayat Samiti, Baripada	Proposal Date			01-07-2023		
Date of Commencement	-	Date of Completion					
Scheme Name	5th SFC Grant in Aid	Scheme Component Name			All Weather Connectivity		
Project Sub-Category	CC Road	Project Type			Upgradation or Improvement		
Name of Executant							

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	13737/PR&DW
Fund Sanction Amount (in Rs.)	143788

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	14.58	235.56432	3434.5277856
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	8.28	1228.056172	10168.30510416

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	9.72	5933.22366072	57670.933982198
---	---	-----	------	---------------	-----------------

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	8.76	7277.32205764	63749.341224926
---	---	-----	------	---------------	-----------------

1	<p>Earth Work (AR0102 aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift</p> <p>- Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	14.58	Cubic Meter	0.516	7.52328	-	-	-	-
---	---	-------	-------------	-------	---------	---	---	---	---

2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	8.28	Cubic Meter	0.1236	1.023408	-	-	-	-
---	--	------	-------------	--------	----------	---	---	---	---

3	<p>Concrete</p> <p>(AR0303)): Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	9.72	Cubic Meter	3.9	37.908	-	-	0.18	1.7496
---	---	------	-------------	-----	--------	---	---	------	--------

4	<p>Concrete</p> <p>(AR0307)): Cement concrete (1:2:4) with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	8.76	Cubic Meter	4.6	40.296	-	-	0.68	5.9568
---	--	------	-------------	-----	--------	---	---	------	--------

5	R.C.C. Work (AR0410 c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	14.4	Square Meter	-	-	0.05	0.72	0.05	0.72
Total Qty				86.750688		8.4264		0.72	
Rate Per Man Day				452		552		502	
Total Amount				39211.310976		4651.3728		361.44	
Total Labour Amount (in Rs.): 44224.123776									

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	14.58	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.28	Cum
i)	BRM029 : Sand for filling and road blinding	1	8.28	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	9.72	Cum
i)	BRM340 : Cement	2.29	22.2588	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.6656	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.3312	1 Cum.
4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	8.76	Cum

i)	BRM340 : Cement	3.23	28.2948	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.942	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	7.884	1 Cum.
5	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	14.4	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.038448	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.8144	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	8.28	1 Cum	557.78	4618.4184
2	BRM340	50.5536	1 Qntl.	459.642	23236.5578112
3	BRM028	8.6076	1 Cum	564.2	4856.40792
4	BRM044	9.3312	1 Cum.	1661.86	15507.148032

5	BRM056	7.884	1 Cum.	2063.23	16266.50532
6	BRM104	0.038448	1Cum.	58620.646	2253.846597408
7	BRM092	1.8144	1Mtr.	276.666	501.9827904
Total: 67240.866871008					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	8.28	1 Cum	602.25	4986.63
2	BRM028	8.6076	1 Cum	602.25	5183.9271
3	BRM044	9.3312	1 Cum.	551.5	5146.1568
4	BRM056	7.884	1 Cum.	551.5	4348.026
Total: 19664.7399					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 1381.2461813892
2	Display Citizen Board @ Rs. 2900	Rs. 2900
3	Any Other Lumpsum @ 1%	Rs. 1381.2461813892
Total Addition Component Amount (in Rs.): 5662.4923627784		

Total Net Amount (in Rs.): 143787.1105017