

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Kendujhar	<b>Block</b>	Kendujhar Sadar	<b>Panchayat</b>	Maidankel

<b>Work Code</b>	OD/361/3452/119460/386090/00015564 (CONSTRUCTION OF CC ROAD FROM KARUNAKAR MAHANTA HOUSE TO UPENDRA MAHANTA HOUSE AT KERI MAHANTA SAHI)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	Maidankel, G.P
<b>Executing Agency</b>	Panchayat Samiti, Kendujhar Sadar	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>	Ranjan Kumar Swain		

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	18204
<b>Fund Sanction Amount (in Rs.)</b>	186532

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</b></p>	Cum	2.80053152	235.56432	659.70530314737
2	<p style="text-align: center;"><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</b></p>	Cum	10.1936090896	1051.841472	10722.060789797

3	<p><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.668597944	6088.56470284	89310.70768199
---	---	-----	--------------	---------------	----------------

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	9.769296	7569.65761308	73950.225840832
---	---	-----	----------	---------------	-----------------



1	<p><b>Earth Work (AR0102 aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b></p> <p>- Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	2.80053152	Cubic Meter	0.516	1.44507426432	-	-	-	-
---	---	------------	-------------	-------	---------------	---	---	---	---

2	<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	10.19360 90896	Cubic Meter	0.1236	1.259930 0834746	-	-	-	-
---	--	-------------------	----------------	--------	---------------------	---	---	---	---

3	<p><b>Concrete</b></p> <p><b>(AR0303)</b> ): <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	14.66859 7944	Cubic Meter	3.9	57.20753 19816	-	-	0.18	2.640347 62992
---	---	------------------	----------------	-----	-------------------	---	---	------	-------------------

4	<p><b>Concrete</b></p> <p><b>(AR0307)</b> ): <b>Cement concrete (1:2:4) with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	9.769296	Cubic Meter	4.6	44.93876 16	-	-	0.68	6.643121 28
---	--	----------	-------------	-----	----------------	---	---	------	----------------

5	R.C.C. Work (AR0410 c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	26.70961 25	Square Meter	-	-	0.05	1.335480 625	0.05	1.335480 625
<b>Total Qty</b>				<b>104.85129792939</b>	<b>10.61894953492</b>	<b>1.335480625</b>			
<b>Rate Per Man Day</b>				<b>452</b>	<b>552</b>	<b>502</b>			
<b>Total Amount</b>				<b>47392.786664086</b>	<b>5861.6601432758</b>	<b>670.41127375</b>			
<b>Total Labour Amount (in Rs.): 53924.858081112</b>									

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>2.80053152</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>10.1936090896</b>	Cum
i)	<b>BRM029 : Sand for filling and road blinding</b>	1	10.1936090896	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>14.668597944</b>	Cum
i)	<b>BRM340 : Cement</b>	2.29	33.59108929176	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	7.04092701312	1 Cum
iii)	<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	14.08185402624	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>9.769296</b>	Cum

i)	<b>BRM340</b> : Cement	3.23	31.55482608	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	4.3961832	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	8.7923664	1 Cum.
5	<b>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	<b>26.7096125</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.071314665375	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.365411175	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	10.1936090896	1 Cum	935.31	9534.1845175938
2	<b>BRM340</b>	65.14591537176	1 Qntl.	584.292	38064.237184396
3	<b>BRM028</b>	11.43711021312	1 Cum	945.31	10811.614655564
4	<b>BRM044</b>	14.08185402624	1 Cum.	1661.86	23402.069932047

5	<b>BRM056</b>	8.7923664	1 Cum.	2036.61	17906.621333904
6	<b>BRM104</b>	0.071314665375	1Cum.	58573.086	4177.1200280711
7	<b>BRM092</b>	3.365411175	1Mtr.	229.106	771.03589265955
<b>Total: 104666.88354424</b>					

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	10.1936090896	1 Cum	50.25	512.2288567524
2	<b>BRM028</b>	11.43711021312	1 Cum	50.25	574.71478820928
3	<b>BRM044</b>	14.08185402624	1 Cum.	424.5	5977.7470341389
4	<b>BRM056</b>	8.7923664	1 Cum.	424.5	3732.3595368
<b>Total: 10797.050215901</b>					

### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 1865	Rs. 1865
2	Display Citizen Board @ Rs. 3000	Rs. 3000
3	Any Other Lumpsum @ Rs. 1275.72	Rs. 1275.72
<b>Total Addition Component Amount (in Rs.): 6140.72</b>		

**Total Net Amount (in Rs.): 186531.99310542**