

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Sonepur	Panchayat	Bisimunda
Work Code	OD/372/3570/121475/419539/00016433 (CC road from Bisimunda to Trisulbandh)						
Project Category	Road						
Financial Year	2024-25	Execution Level			Bisimunda, G.P		
Executing Agency	Panchayat Samiti, Sonepur	Proposal Date			-		
Date of Commencement	-	Date of Completion					
Scheme Name	5th SFC Grant in Aid	Scheme Component Name			MAINTENANCE OF ROADS AND BRIDGES		
Project Sub-Category	CC Road	Project Type			Upgradation or Improvement		
Name of Executant	MISS MOHINI ORAM						

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	500000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	12.5	235.56432	2944.554
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	27.7	645.558872	17881.9807544

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	41.7	5813.64389262	242428.95032225
---	---	-----	------	---------------	-----------------

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	31.025	7321.01832394	227134.59350024
---	---	-----	--------	---------------	-----------------

5	<p style="text-align: center;">R.C.C.</p> <p>Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	40	215.38264180804	8615.3056723216
Total Amount (in Rs.): 499005.38424921					

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	12.5	235.56432	Cum
i	Un-Skilled	0.516	6.45	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	27.7	645.558872	Cum
i	Un-Skilled	0.1236	3.42372	-

3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	41.7	5813.64389262	Cum
i	Skilled	0.18	7.506	-
ii	Un-Skilled	3.9	162.63	-

4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	31.025	7321.01832394	Cum
i	Un-Skilled	4.6	142.715	-
ii	Skilled	0.68	21.097	-

5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	40	215.38264180804	Sqm
i	Semi-Skilled	0.05	2	-
ii	Skilled	0.05	2	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
2	Un-Skilled	315.21872	452	142478.86144
4	Skilled	30.603	552	16892.856
3	Semi-Skilled	2	502	1004
Total: 160375.71744				

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	12.5	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	27.7	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	27.7	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	41.7	Cum
i)	BRM340 : Cement	2.29	95.493	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	20.016	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	40.032	1 Cum.
4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	31.025	Cum

i)	BRM340 : Cement	3.23	100.21075	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	13.96125	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	27.9225	1 Cum.
5	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	40	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1068	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	5.04	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	27.7	1 Cum	413.05	11441.485
2	BRM340	195.70375	1 Qntl.	580.397	113585.86938875
3	BRM028	33.97725	1 Cum	417.99	14202.1507275
4	BRM044	40.032	1 Cum.	1726.96	69133.66272

5	BRM056	27.9225	1 Cum.	2111.71	58964.222475
6	BRM104	0.1068	1Cum.	58620.646	6260.6849928
7	BRM092	5.04	1Mtr.	276.666	1394.39664
Total: 274982.47194405					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	27.7	1 Cum	170.25	4715.925
2	BRM028	33.97725	1 Cum	170.25	5784.6268125
3	BRM044	40.032	1 Cum.	279.5	11188.944
4	BRM056	27.9225	1 Cum.	279.5	7804.33875
Total: 29493.8345625					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 994.61	Rs. 994.61
Total Addition Component Amount (in Rs.): 994.61		

Total Net Amount (in Rs.): 499999.99424921