

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Nayagarh	Panchayat	Ikiri
Work Code	OD/367/3527/120664/406317/00016409 (Construction of C.C Road at Periphery of Ramachandi Mandir Tipura)						
Project Category	Road						
Financial Year	2024-25		Execution Level		Ikiri, G.P		
Executing Agency	Panchayat Samiti, Nayagarh		Proposal Date		-		
Date of Commencement	-		Date of Completion				
Scheme Name	5th SFC Grant in Aid		Scheme Component Name		All Weather Connectivity		
Project Sub-Category	CC Road		Project Type		New Work		
Name of Executant							

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	143788

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	2.0069532	235.56432	472.76656582982
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	5.82016428	779.535372	4537.0239271109

3	<p>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	11.921302008	5130.2318043	61159.042710107
---	--	-----	--------------	--------------	-----------------

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	10.58325675264	6905.5061581	73082.744678109
---	--	-----	----------------	--------------	-----------------

5	<p style="text-align: center;">R.C.C.</p> <p>Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	14.57369361	215.22489289764	3136.6216463353
Total Amount (in Rs.): 142388.19952749					

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	2.0069532	235.56432	Cum
i	Un-Skilled	0.516	1.0355878512	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	5.82016428	779.535372	Cum
i	Un-Skilled	0.1236	0.719372305008	-

3	Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	11.921302008	5130.2318043	Cum
i	Un-Skilled	3.9	46.4930778312	-
ii	Skilled	0.18	2.14583436144	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	10.58325675264	6905.5061581	Cum
i	Un-Skilled	4.6	48.682981062144	-
ii	Skilled	0.68	7.1966145917952	-

5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	14.57369361	215.22489289764	Sqm
i	Semi-Skilled	0.05	0.7286846805	-
ii	Skilled	0.05	0.7286846805	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
2	Un-Skilled	96.931019049552	452	43812.820610398
4	Skilled	10.071133633735	552	5559.2657658218
3	Semi-Skilled	0.7286846805	502	365.799709611
Total:				49737.88608583

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.0069532	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.82016428	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	5.82016428	1 Cum

3	<p>Concrete (AR0303a) ::Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.921302008	Cum
i)	BRM340 : Cement	2.29	27.29978159832	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.72222496384	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	11.44444992768	1 Cum.
4	<p>Concrete (AR0307) ::Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	10.58325675264	Cum

i)	BRM340 : Cement	3.23	34.183919311027	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.762465538688	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	9.524931077376	1 Cum.
5	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	14.57369361	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0389117619387	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.83628539486	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	5.82016428	1 Cum	410.7	2390.341469796
2	BRM340	61.483700909347	1 Qntl.	579.287	35616.708648673
3	BRM028	10.484690502528	1 Cum	417.13	4373.4789493195
4	BRM045	11.44444992768	1 Cum.	1038.44	11884.3745829

5	BRM056	9.524931077376	1 Cum.	1672.63	15931.685467951
6	BRM104	0.0389117619387	1Cum.	58573.086	2279.181978447
7	BRM092	1.83628539486	1Mtr.	229.106	420.7040016748
Total: 72896.475098762					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	5.82016428	1 Cum	305.25	1776.60514647
2	BRM028	10.484690502528	1 Cum	305.25	3200.4517758967
3	BRM045	11.44444992768	1 Cum.	199.5	2283.1677605722
4	BRM056	9.524931077376	1 Cum.	199.5	1900.2237499365
Total: 9160.4484328753					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 1399.8	Rs. 1399.8
Total Addition Component Amount (in Rs.): 1399.8		

Total Net Amount (in Rs.): 143787.99952749