

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Nayagarh	<b>Block</b>	Nayagarh	<b>Panchayat</b>	Biruda
<b>Work Code</b>	OD/367/3527/120659/406303/00017156 (Maintenance of Kani Pokhari Backside Road and Bridge)						
<b>Project Category</b>	CD Work						
<b>Financial Year</b>	2024-25			<b>Execution Level</b>	Biruda, G.P		
<b>Executing Agency</b>	Panchayat Samiti, Nayagarh			<b>Proposal Date</b>	-		
<b>Date of Commencement</b>	-			<b>Date of Completion</b>			
<b>Scheme Name</b>	5th SFC Grant in Aid			<b>Scheme Component Name</b>	MAINTENANCE OF ROADS AND BRIDGES		
<b>Project Sub-Category</b>	Humepipe Culvert			<b>Project Type</b>	Renovation or Rejuvenation		
<b>Name of Executant</b>							

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	29781
<b>Fund Sanction Amount (in Rs.)</b>	300000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</b></p>	Cum	4.15125	235.56432	977.8863834
2	<p style="text-align: center;"><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</b></p>	Cum	12.6075	779.535372	9827.99220249

3	<p><b>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	25.215	5130.2318043	129358.79494542
---	--	-----	--------	--------------	-----------------

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	22.41246	6905.5061581	154769.38054817
---	--	-----	----------	--------------	-----------------

5	<p style="text-align: center;"><b>R.C.C.</b></p> <p><b>Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>  - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor  R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	15.375	215.22489289764	3309.0827283012
<b>Total Amount (in Rs.): 298243.13680779</b>					

### LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	4.15125	235.56432	Cum
i	Un-Skilled	0.516	2.142045	-
2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	12.6075	779.535372	Cum
i	Un-Skilled	0.1236	1.558287	-

3	<b>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	25.215	5130.2318043	Cum
i	Un-Skilled	3.9	98.3385	-
ii	Skilled	0.18	4.5387	-

4	<b>Concrete (AR0307)</b> <b>: Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</b>	22.41246	6905.5061581	Cum
i	Un-Skilled	4.6	103.097316	-
ii	Skilled	0.68	15.2404728	-

5	<b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	15.375	215.22489289764	Sqm
i	Semi-Skilled	0.05	0.76875	-
ii	Skilled	0.05	0.76875	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
2	Un-Skilled	205.136148	452	92721.538896
4	Skilled	20.5479228	552	11342.4533856
3	Semi-Skilled	0.76875	502	385.9125
<b>Total: 104449.9047816</b>				

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	4.15125	Cum
2	<p><b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	12.6075	Cum
i)	<p><b>BRM029</b> : Sand for filling and road blinding</p>	1	12.6075	1 Cum

3	<p><b>Concrete (AR0303a)</b>  <b>::Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	25.215	Cum
i)	<b>BRM340 : Cement</b>	2.29	57.74235	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	12.1032	1 Cum
iii)	<b>BRM045 : Granite Stone broken metal 40mm. size (Hand broken)</b>	0.96	24.2064	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>::Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	22.41246	Cum

i)	<b>BRM340</b> : Cement	3.23	72.3922458	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	10.085607	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	20.171214	1 Cum.
5	<b>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	<b>15.375</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.04105125	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.93725	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	12.6075	1 Cum	410.7	5177.90025
2	<b>BRM340</b>	130.1345958	1 Qntl.	579.287	75385.279597195
3	<b>BRM028</b>	22.188807	1 Cum	417.13	9255.61706391
4	<b>BRM045</b>	24.2064	1 Cum.	1038.44	25136.894016

5	<b>BRM056</b>	20.171214	1 Cum.	1672.63	33738.97767282
6	<b>BRM104</b>	0.04105125	1Cum.	58573.086	2404.4983966575
7	<b>BRM092</b>	1.93725	1Mtr.	229.106	443.8355985
<b>Total: 151543.00259508</b>					

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	12.6075	1 Cum	305.25	3848.439375
2	<b>BRM028</b>	22.188807	1 Cum	305.25	6773.13333675
3	<b>BRM045</b>	24.2064	1 Cum.	199.5	4829.1768
4	<b>BRM056</b>	20.171214	1 Cum.	199.5	4024.157193
<b>Total: 19474.90670475</b>					

### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 1756	Rs. 1756
<b>Total Addition Component Amount (in Rs.): 1756</b>		

**Total Net Amount (in Rs.): 299999.13680779**