

**ESTIMATION DPR**

<b>State</b>	Odisha	<b>District</b>	Kandhamal	<b>Block</b>	Phulbani	<b>Gram Panchayat</b>	Alami
--------------	--------	-----------------	-----------	--------------	----------	-----------------------	-------

<b>Work Code</b>	OD/359/3430/118977/415448/00013543 (Imp. Of road from Nedisahi to New AWC)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Phulbani	<b>Proposal Date</b>	13-06-2023
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>			

**Administrative Approval Details**

<b>Approval No.</b>	
---------------------	--

**Technical Sanction Details**

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	12942
<b>Fund Sanction Amount (in Rs.)</b>	300000

**ACTIVITY STATEMENT**

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</b></p>	Cum	27.60888	240.77592	6647.5534821696
2	<p style="text-align: center;"><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</b></p>	Cum	6.37128	543.847832	3465.006815065

3	<p><b>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	42.16937856	5870.3119404	247547.40648002
---	--	-----	-------------	--------------	-----------------

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	1.22328576	8079.5229568	9883.5653806465
---	--	-----	------------	--------------	-----------------

5	<p style="text-align: center;"><b>R.C.C.</b></p> <p><b>Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>  - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor  <b>R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b></p>	Sqm	124.4156976	216.23489289764	26903.015045321
<b>Total Amount (in Rs.): 294446.54720322</b>					

### LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	27.60888	Cum
i	Un-Skilled	0.516	14.24618208	-
2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.37128	Cum
i	Un-Skilled	0.1236	0.787490208	-

3	<b>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	42.16937856	Cum
i	Un-Skilled	3.9	164.460576384	-
ii	Skilled	0.18	7.5904881408	-

4	<b>Concrete (AR0307)</b> <b>: Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</b>	-	1.22328576	Cum
i	Un-Skilled	4.6	5.627114496	-
ii	Skilled	0.68	0.8318343168	-

5	<b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	124.4156976	Sqm
i	Semi-Skilled	0.05	6.22078488	-
ii	Skilled	0.05	6.22078488	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	185.121363168	462	85526.069783616
2	Skilled	14.6431073376	562	8229.4263237312
3	Semi-Skilled	6.22078488	512	3185.04185856
<b>Total: 96940.537965907</b>				

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	27.60888	Cum
2	<p><b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.37128	Cum
i)	<p><b>BRM029</b> : Sand for filling and road blinding</p>	1	6.37128	1 Cum

3	<p><b>Concrete (AR0303a)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>42.16937856</b>	Cum
i)	<b>BRM340 : Cement</b>	2.29	96.5678769024	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	20.2413017088	1 Cum
iii)	<b>BRM045 : Granite Stone broken metal 40mm. size (Hand broken)</b>	0.96	40.4826034176	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	<b>1.22328576</b>	Cum

i)	<b>BRM340</b> : Cement	3.23	3.9512130048	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	0.550478592	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.100957184	1 Cum.
5	<b>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	<b>124.4156976</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.332189912592	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	15.6763778976	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	6.37128	1 Cum	411.11	2619.2969208
2	<b>BRM340</b>	100.5190899072	1 Qntl.	563.532	56645.723773584
3	<b>BRM028</b>	20.7917803008	1 Cum	1076.79	22388.381110098
4	<b>BRM045</b>	40.4826034176	1 Cum.	1453.97	58860.490891088

5	<b>BRM056</b>	1.100957184	1 Cum.	2626.53	2891.6970724915
6	<b>BRM104</b>	0.332189912592	1Cum.	58573.086	19457.388318584
7	<b>BRM092</b>	15.6763778976	1Mtr.	229.106	3591.5522346075
<b>Total: 166454.53032125</b>					

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	6.37128	1 Cum	70.25	447.58242
2	<b>BRM028</b>	20.7917803008	1 Cum	70.25	1460.6225661312
3	<b>BRM045</b>	40.4826034176	1 Cum.	344.5	13946.256877363
4	<b>BRM056</b>	1.100957184	1 Cum.	344.5	379.279749888
<b>Total: 16233.741613382</b>					

### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 2553.45	Rs. 2553.45
2	Display Citizen Board @ Rs. 3000	Rs. 3000
<b>Total Addition Component Amount (in Rs.): 5553.45</b>		

**Total Net Amount (in Rs.): 299999.99720322**