

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Puri	<b>Block</b>	Sadar	<b>Gram Panchayat</b>	Chalisibatia
--------------	--------	-----------------	------	--------------	-------	-----------------------	--------------

<b>Work Code</b>	OD/369/3545/121067/409754/00013572 (Imp of Kanchi Harijan Sahi CC Road)
<b>Project Category</b>	Road

<b>Financial Year</b>	2021-22	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Sadar	<b>Proposal Date</b>	15-07-2021
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>			

## Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

## Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	11088
<b>Fund Sanction Amount (in Rs.)</b>	300000

## ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	21.86623296	240.77592	5264.8623578783
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	21.86623296	723.405632	15818.156073888

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	21.86623296	6212.3555104	135840.81282075
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	16.565328	7758.9257268	128529.14959208

5	<b>R.C.C. Work (AR0410c) :</b> <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	Sqm	43.478604	216.23489289764	9401.5912792789
<b>Total Amount (in Rs.): 294854.57212387</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	21.86623296	Cum
i	Un-Skilled	0.516	11.28297620736	-

2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	21.86623296	Cum
i	Un-Skilled	0.1236	2.702666393856	-
3	<p><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	21.86623296	Cum
i	Skilled	0.18	3.9359219328	-
ii	Un-Skilled	3.9	85.278308544	-

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	16.565328	Cum
i	Un-Skilled	4.6	76.2005088	-
ii	Skilled	0.68	11.26442304	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	43.478604	Sqm
i	Semi-Skilled	0.05	2.1739302	-
ii	Skilled	0.05	2.1739302	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	175.46445994522	462	81064.58049469
2	Skilled	17.3742751728	562	9764.3426471136
3	Semi-Skilled	2.1739302	512	1113.0522624
<b>Total:</b>				<b>91941.975404203</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>21.86623296</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>21.86623296</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	21.86623296	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>21.86623296</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	50.0736734784	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	10.4957918208	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	20.9915836416	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	<b>16.565328</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	53.50600944	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	7.4543976	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	14.9087952	1 Cum.
5	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	<b>43.478604</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.11608787268	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	5.478304104	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	21.86623296	1 Cum	583.89	12767.474763014
2	<b>BRM340</b>	103.5796829184	1 Qntl.	600.588	62208.714604596
3	<b>BRM028</b>	17.9501894208	1 Cum	806.71	14480.597307654
4	<b>BRM044</b>	20.9915836416	1 Cum.	2003.31	42052.649425054
5	<b>BRM056</b>	14.9087952	1 Cum.	2414.93	36003.696792336
6	<b>BRM104</b>	0.11608787268	1Cum.	58573.086	6799.6249500427
7	<b>BRM092</b>	5.478304104	1Mtr.	229.106	1255.112340051
<b>Total: 175567.87018275</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	21.86623296	1 Cum	75.25	1645.43403024
2	<b>BRM028</b>	17.9501894208	1 Cum	75.25	1350.7517539152
3	<b>BRM044</b>	20.9915836416	1 Cum.	170.5	3579.0650108928

4	BRM056	14.9087952	1 Cum.	170.5	2541.9495816
					<b>Total: 9117.200376648</b>

#### ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 3000	Rs. 3000
2	Display Citizen Board @ Rs. 1500	Rs. 1500
3	Any Other Lumpsum @ Rs. 143	Rs. 143
4	Provision for survey investigation and quality control @ Rs. 500	Rs. 500
		<b>Total Addition Component Amount (in Rs.): 5143</b>

**Total Net Amount (in Rs.): 299997.57212387**