

ESTIMATION DPR							
State	Odisha	District	Khordha	Block	Bhubaneswar	Gram Panchayat	Tikarapada

Work Code	OD/362/3460/119616/407758/00068142 (Construction of CC Road from Jatra padia to Behera house, Palaspur sasan, Tikarpada G.P)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhubaneswar	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

### Administrative Approval Details

Approval No.	
--------------	--

### Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	205000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	11.468304	240.77592	2761.2914464397
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.783068608	502.629732	7430.4098125767

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.783068608	5720.0028415	84559.194443849
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	14.783068608	7166.3049645	105939.97795605
<b>Total Amount (in Rs.): 200690.87365892</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b></p> <p>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	11.468304	Cum
i	Un-Skilled	0.516	5.917644864	-
2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b></p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	14.783068608	Cum
i	Un-Skilled	0.1236	1.8271872799488	-

3	<p><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	14.783068608	Cum
i	Skilled	0.18	2.66095234944	-
ii	Un-Skilled	3.9	57.6539675712	-
4	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	14.783068608	Cum
i	Un-Skilled	4.6	68.0021155968	-

ii	Skilled	0.68	10.05248665344	-
----	---------	------	----------------	---

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	133.40091531195	462	61631.22287412
2	Skilled	12.71343900288	562	7144.9527196186
<b>Total: 68776.175593739</b>				

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>11.468304</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>14.783068608</b>	Cum
i)	<b>BRM029 : Sand for filling and road blinding</b>	1	14.783068608	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>14.783068608</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	33.85322711232	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	7.09587293184	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	14.19174586368	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	<b>14.783068608</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	47.74931160384	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	6.6523808736	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	13.3047617472	1 Cum.
------	--	-----	---------------	--------

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	14.783068608	1 Cum	397.3	5873.3131579584
2	<b>BRM340</b>	81.60253871616	1 Qntl.	569.387	46463.424711978
3	<b>BRM028</b>	13.74825380544	1 Cum	403.69	5550.0325787181
4	<b>BRM044</b>	14.19174586368	1 Cum.	1792.06	25432.460092466
5	<b>BRM056</b>	13.3047617472	1 Cum.	2169.52	28864.946705785
<b>Total: 112184.17724691</b>					

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	14.783068608	1 Cum	43.25	639.367717296
2	<b>BRM028</b>	13.74825380544	1 Cum	43.25	594.61197708528
3	<b>BRM044</b>	14.19174586368	1 Cum.	309.5	4392.345344809
4	<b>BRM056</b>	13.3047617472	1 Cum.	309.5	4117.8237607584
<b>Total: 9744.1487999486</b>					

### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 2050	Rs. 2050
2	Display Citizen Board @ Rs. 2259	Rs. 2259
<b>Total Addition Component Amount (in Rs.): 4309</b>		

**Total Net Amount (in Rs.): 204999.87365892**