

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Sambalpur	<b>Block</b>	Jamankira	<b>Gram Panchayat</b>	Dhudipali

<b>Work Code</b>	OD/371/3560/121314/381532/00069079 (Construction of CC Road, RD road to Ayurvedic Hospital)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Jamankira	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	257165

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	6.21	240.77592	1495.2184632
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	13.68	668.279832	9142.06810176

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	21.96	5358.7941478	117679.11948569
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	15.75	6901.5292326	108699.08541345
<b>Total Amount (in Rs.): 237015.4914641</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>                      Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	6.21	Cum
i	Un-Skilled	0.516	3.20436	-
2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b>                      Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.68	Cum
i	Un-Skilled	0.1236	1.690848	-

3	<p><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	21.96	Cum
i	Skilled	0.18	3.9528	-
ii	Un-Skilled	3.9	85.644	-
4	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	15.75	Cum
i	Un-Skilled	4.6	72.45	-

ii	Skilled	0.68	10.71	-
----	---------	------	-------	---

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	162.989208	462	75301.014096
2	Skilled	14.6628	562	8240.4936
<b>Total: 83541.507696</b>				

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>6.21</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>13.68</b>	Cum
i)	<b>BRM029 : Sand for filling and road blinding</b>	1	13.68	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	21.96	Cum
i)	<b>BRM340</b> : Cement	2.29	50.2884	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	10.5408	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	21.0816	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	15.75	Cum
i)	<b>BRM340</b> : Cement	3.23	50.8725	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	7.0875	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	14.175	1 Cum.
------	--	-----	--------	--------

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	13.68	1 Cum	541.31	7405.1208
2	<b>BRM340</b>	101.1609	1 Qntl.	580.622	58736.2440798
3	<b>BRM028</b>	17.6283	1 Cum	548.19	9663.657777
4	<b>BRM044</b>	21.0816	1 Cum.	1421.31	29963.488896
5	<b>BRM056</b>	14.175	1 Cum.	1867.93	26477.90775
<b>Total: 132246.4193028</b>					

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	13.68	1 Cum	63.25	865.26
2	<b>BRM028</b>	17.6283	1 Cum	63.25	1114.989975
3	<b>BRM044</b>	21.0816	1 Cum.	201.5	4247.9424
4	<b>BRM056</b>	14.175	1 Cum.	201.5	2856.2625
<b>Total: 9084.454875</b>					

### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 5000	Rs. 5000
2	Display Citizen Board @ Rs. 6000	Rs. 6000
3	Any Other Lumpsum @ Rs. 7000	Rs. 7000
4	Provision for survey investigation and quality control @ Rs. 2149	Rs. 2149
<b>Total Addition Component Amount (in Rs.): 20149</b>		

**Total Net Amount (in Rs.): 257164.4914641**