

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Badasahi	Gram Panchayat	Suhagpur

Work Code	OD/365/3487/120063/390666/00065132 (CONSTRUCTION OF MARKET COMPLEX IN FRONT OF FIRE STATION OF VILLAGE GUHALDIHI UNDER SUHAGPUR GP)						
Project Category	Building						

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Badasahi	Proposal Date	06-02-2024
Date of Commencement	-	Date of Completion	
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	3064
Fund Sanction Amount (in Rs.)	500000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	21.60180556	216.70813962884	4681.2870955315
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	15.23587972512	1720.629132	26215.29850669

3	<p style="text-align: center;">Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	4.79080329312	6753.5835438	32355.090281998
4	<p style="text-align: center;">Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in- charge.</p>	Cum	13.04413392	5699.56277864	74345.860170027

5	<p style="text-align: center;">R.C.C. Work (AR0404Aa) :</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	Cum	10.21043493216	7307.9907604893	74617.764144802
---	--	-----	----------------	-----------------	-----------------

6	<p style="text-align: center;">R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm</p>	Sqm	25.28633854	1048.946881161	26524.025947514
7	<p style="text-align: center;">R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	Sqm	6.317404	500.42561591462	3161.3907876815

8	<p>R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	Sqm	24.03865125	664.51849854133	15974.128435609
9	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	9.5	8428.8790379	80074.35086005

10	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	74.786915	265.86739646	19883.402380325
11	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	51.3010366	187.985108296	9643.8309209481

12	<p style="text-align: center;">Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in- charge.</p>	Sqm	22.4360745	390.767726996	8767.2938350779
13	<p style="text-align: center;">Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in- charge.</p>	Qntl	4	15771.744505087	63086.978020348

14	<p style="text-align: center;">Painting (AR0920bk) : Finishing wall two coats with plastic emulsion paint of approved shades with one coat water bound Primer on new work (Inside)(For repair and maintenance) . - Finishing wall two coats with plastic emulsion paint of approved shades with one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For repair and maintenance).</p>	Sqm	152.7975641	169.05399611528	25831.038807786
15	<p style="text-align: center;">Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	8.454173	66.12545887751	559.03606905486

16	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	14.748663696	240.77592	3551.123070175
17	<p style="text-align: center;">Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	3.09674790144	5666.23277864	17546.894466324
Total Amount (in Rs.): 486818.79379994					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	21.60180556	Sqm
i	Semi-Skilled	0.05	1.080090278	-
ii	Skilled	0.05	1.080090278	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	15.23587972512	Cum
i	Un-Skilled	0.1236	1.8831547340248	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	4.79080329312	Cum
	i Skilled	0.18	0.8623445927616	-
	ii Un-Skilled	3.9	18.684132843168	-
4	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	13.04413392	Cum
	i Un-Skilled	2.96	38.6106364032	-

	ii	Skilled	1.05	13.696340616	-
	iii	Highly-Skilled	0.35	4.565446872	-
5		R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	10.21043493216	Cum
	i	Un-Skilled	1.3333	13.613572895049	-
	ii	Skilled	0.175	1.786826113128	-
	iii	Semi-Skilled	0.1323	1.3508405415248	-

6	<p>R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	25.28633854	Sqm
i	Semi-Skilled	0.6547619047619	16.556531186905	-
ii	Skilled	0.6547619047619	16.556531186905	-
7	<p>R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	-	6.317404	Sqm
i	Semi-Skilled	0.16025641025641	1.0124044871795	-
ii	Skilled	0.16025641025641	1.0124044871795	-

8	R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	24.03865125	Sqm
i	Semi-Skilled	0.305555555555556	7.3451434375	-
ii	Skilled	0.305555555555556	7.3451434375	-
9	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	9.5	Qntl
i	Un-Skilled	0.8	7.6	-

	ii	Highly-Skilled	0.3	2.85	-
	iii	Semi-Skilled	0.044	0.418	-
10		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	74.786915	Sqm
	i	Un-Skilled	0.24	17.9488596	-
	ii	Skilled	0.16	11.9659064	-
11		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	51.3010366	Sqm
	i	Un-Skilled	0.12	6.156124392	-

	ii	Skilled	0.14	7.182145124	-
12		Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	22.4360745	Sqm
	i	Un-Skilled	0.36	8.07698682	-
	ii	Highly-Skilled	0.13	2.916689685	-
13		Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	4	Qntl
	i	Un-Skilled	6.3976377952756	25.590551181102	-
	ii	Semi-Skilled	1.9685039370079	7.8740157480315	-
	iii	Skilled	3.9370078740157	15.748031496063	-

	iv	Highly-Skilled	3.4448818897638	13.779527559055	-
14		<p>Painting (AR0920bk) : Finishing wall two coats with plastic emulsion paint of approved shades with one coat water bound Primer on new work (Inside)(For repair and maintenance) . - Finishing wall two coats with plastic emulsion paint of approved shades with one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For repair and maintenance).</p>	-	152.7975641	Sqm
	i	Highly-Skilled	0.10991870967742	16.795311087725	-
	ii	Un-Skilled	0.12011870967742	18.353846241545	-
15		<p>Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	8.454173	Sqm
	i	Highly-Skilled	0.053763440860215	0.45452543010753	-

	ii	Un-Skilled	0.053763440860215	0.45452543010753	-
16		<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	14.748663696	Cum
	i	Un-Skilled	0.516	7.610310467136	-
17		<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	3.09674790144	Cum
	i	Un-Skilled	2.96	9.1663737882624	-

ii	Skilled	1.05	3.251585296512	-
iii	Highly-Skilled	0.35	1.083861765504	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Semi-Skilled	35.637025679141	512	18246.15714772
2	Skilled	80.487349028049	562	45233.890153763
3	Un-Skilled	173.74907479559	462	80272.072555565
4	Highly-Skilled	42.445362399391	612	25976.561788428
Total:				169728.68164548

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	21.60180556	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0576768208452	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.72182750056	1Mtr.

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.23587972512	Cum
i)	BRM029 : Sand for filling and road blinding	1	15.23587972512	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.79080329312	Cum
i)	BRM340 : Cement	2.29	10.970939541245	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.2995855806976	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	4.5991711613952	1 Cum.

4	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	13.04413392	Cum
i)	<p>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</p>	1	13.04413392	1 Cum
ii)	<p>BRM340 : Cement</p>	0.672	8.76565799424	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	3.6523574976	1 Cum
iv)	<p>BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	350	4565.446872	1000 Nos

5	R.C.C. Work (AR0404Aa) ∴Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	10.21043493216	Cum
i)	BRM340 : Cement	3.4733	35.463903649871	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.594695719472	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.6757565755776	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	5.5136348633664	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.040892791903301	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.9297722021782	1Mtr.

6	R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	25.28633854	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	13.967691764952	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.13124813813619	1Cum.
7	R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	6.317404	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	1.7008395384615	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.03344984425641	1Cum.

8	R.C.C. Work (AR0410a) :-Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	24.03865125	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	14.957383	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.005022222222222	0.1207274485	1Cum.
9	R.C.C. Work (AR0409) :-Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	9.5	Qntl
i)	BRM162 : Binding Wire.	0.8	7.6	1 Kg.
ii)	BRM341 : Steel	1.05	9.975	1 Qntl.

10	Plastering (AR1014) ::16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	74.786915	Sqm
i)	BRM340 : Cement	0.043	3.215837345	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.34616447	1 Cum
11	Plastering (AR1004) ::12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	51.3010366	Sqm
i)	BRM340 : Cement	0.0358	1.83657711028	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.769515549	1 Cum
12	Flooring (AR0802ii) ::2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	22.4360745	Sqm
i)	BRM340 : Cement	0.0858	1.9250151921	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.269232894	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.5160297135	1 Cum.
13	Iron Work(AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	4	Qntl
i)	BRM341 : Steel	1	4	1 Qntl.
14	Painting(AR0920bk) : Finishing wall two coats with plastic emulsion paint of approved shades with one coat water bound Primer on new work (Inside)(For repair and maintenance) . - Finishing wall two coats with plastic emulsion paint of approved shades with one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For repair and maintenance).	-	152.7975641	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	19.0996955125	1 Litre
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	12.8349953844	1 Ltr

15	Painting(AR0901b) :.Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	8.454173	Sqm
i)	BRM137 : Red oxide Primer	0.054	0.456525342	1 Litre
16	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	14.748663696	Cum
17	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	3.09674790144	Cum

i)	BRM340 : Cement	0.672	2.0810145897677	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.8670894124032	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	1083.861765504	1000 Nos

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM104	0.3839950436411	1Cum.	58715.766	22546.563127591
2	BRM092	4.6515997027382	1Mtr.	371.786	1729.3996470822
3	BRM029	15.23587972512	1 Cum	857.24	13060.805535562
4	BRM340	64.258945422504	1 Qntl.	650.622	41808.28358868
5	BRM028	13.798641123173	1 Cum	863.66	11917.334392439
6	BRM044	4.5991711613952	1 Cum.	1792.06	8241.9906714899
7	BRMMR0025	13.04413392	1 Cum	33	430.45641936
8	BRM005	5649.308637504	1000 Nos	7.0421	39782.996356167
9	BRM060	3.6757565755776	1 Cum.	2176.81	8001.4236712831
10	BRM052	5.5136348633664	1 Cum.	2179.1	12014.761730762
11	BRM084	28.925074764952	1Mtr	392.846	11363.099921112
12	BRM094	1.7008395384615	1Mtr.	382.786	651.05756356954
13	BRM162	7.6	1 Kg.	90	684
14	BRM341	13.975	1 Qntl.	6219.332	86915.1647
15	BRM057	0.5160297135	1 Cum.	1882	971.167920807
16	BRM140	19.0996955125	1 Litre	249.76622	4770.4587513081
17	BRM253	12.8349953844	1 Ltr	159.45622	2046.6198477139
18	BRM137	0.456525342	1 Litre	143.12622	65.340746534667
Total:					267000.92459146

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	15.23587972512	1 Cum	789.25	12024.918073051
2	BRM028	13.798641123173	1 Cum	789.25	10890.577506464
3	BRM044	4.5991711613952	1 Cum.	551.5	2536.4428955095
4	BRM060	3.6757565755776	1 Cum.	551.5	2027.179751431
5	BRM052	5.5136348633664	1 Cum.	551.5	3040.7696271466

6	BRM057	0.5160297135	1 Cum.	551.5	284.59038699525
					Total: 30804.478240597

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for EI Work @ Rs. 3181	Rs. 3181
2	Provision for Contingency @ Rs. 5000	Rs. 5000
3	Display Citizen Board @ Rs. 5000	Rs. 5000
		Total Addition Component Amount (in Rs.): 13181

Total Net Amount (in Rs.): 499999.79379994