

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Tirtol	Gram Panchayat	Gobindapur

Work Code	OD/355/3393/118214/397702/00069730 (CONSTRUCTION OF CC ROAD FROM JARA BIBI HOUSE TO RABI MALLICK HOUSE, VILL- BARABATIA, GP- GOBINDAPUR.)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Tirtol	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

### Administrative Approval Details

Approval No.	
--------------	--

### Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	78585

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0101a) :</b>  <b>Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift</b> - Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.</p>	Cum	1.2	149.3184	179.18208
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	5.6	798.771832	4473.1222592

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	5.18	6775.74905228	35098.38009081
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	4.2	8222.32327736	34533.757764912

5	<p><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	12	216.23489289764	2594.8187147717
<b>Total Amount (in Rs.): 76879.260909694</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	<p><b>Earth Work (AR0101a) :</b>  <b>Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift</b> - Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.</p>	-	1.2	Cum
i	Un-Skilled	0.32	0.384	-

2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.6	Cum
i	Un-Skilled	0.1236	0.69216	-
3	<p><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.18	Cum
i	Skilled	0.18	0.9324	-
ii	Un-Skilled	3.9	20.202	-

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	4.2	Cum
i	Un-Skilled	4.6	19.32	-
ii	Skilled	0.68	2.856	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	12	Sqm
i	Semi-Skilled	0.05	0.6	-
ii	Skilled	0.05	0.6	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	40.59816	462	18756.34992
2	Skilled	4.3884	562	2466.2808
3	Semi-Skilled	0.6	512	307.2
				<b>Total: 21529.83072</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0101a)</b> :.Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift - Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.2	Cum
2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.6	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	5.6	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.18	Cum
i)	<b>BRM340</b> : Cement	2.29	11.8622	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	2.4864	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	4.9728	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	4.2	Cum
i)	<b>BRM340</b> : Cement	3.23	13.566	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.89	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	3.78	1 Cum.
5	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	12	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.03204	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.512	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	5.6	1 Cum	534.51	2993.256
2	<b>BRM340</b>	25.4282	1 Qntl.	603.877	15355.5051314
3	<b>BRM028</b>	4.3764	1 Cum	543.02	2376.472728
4	<b>BRM044</b>	4.9728	1 Cum.	2501.16	12437.768448
5	<b>BRM056</b>	3.78	1 Cum.	2902.53	10971.5634
6	<b>BRM104</b>	0.03204	1Cum.	58573.086	1876.68167544
7	<b>BRM092</b>	1.512	1Mtr.	229.106	346.408272
<b>Total: 46357.65565484</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	5.6	1 Cum	199.25	1115.8
2	<b>BRM028</b>	4.3764	1 Cum	199.25	871.9977
3	<b>BRM044</b>	4.9728	1 Cum.	444.5	2210.4096

4	BRM056	3.78	1 Cum.	444.5	1680.21
					<b>Total: 5878.4173</b>

#### ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 768.79260909694
2	Display Citizen Board @ Rs. 936	Rs. 936
		<b>Total Addition Component Amount (in Rs.): 1704.7926090969</b>

**Total Net Amount (in Rs.): 78584.053518791**