

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Balasore	<b>Block</b>	Khaira	<b>Gram Panchayat</b>	Baunsagfadia
--------------	--------	-----------------	----------	--------------	--------	-----------------------	--------------

<b>Work Code</b>	OD/346/3304/116205/393518/00065271 (All weather connectivity of CC road from Rama Majhi house to Banku Dehuri house.)
<b>Project Category</b>	Road

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Khaira	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	All Weather Connectivity
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

## Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

## Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	PLChallanNo8443/42Dt23/06/23
<b>Fund Sanction Amount (in Rs.)</b>	150000

## ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	1.72125	240.77592	414.435523
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	7.20375	1503.287232	10829.30539752

3	<p style="text-align: center;"><b>Concrete (AR0303a) :</b>  <b>Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	10.0725	6731.1701187	67799.711020606
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	7.7775	8315.4280609	64673.24174365

5	<b>R.C.C. Work (AR0410c) :</b> <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	Sqm	20.4	216.23489289764	4411.1918151119
<b>Total Amount (in Rs.): 148127.88552919</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.72125	Cum
i	Un-Skilled	0.516	0.888165	-

2	<p><b>Earth Work (AR0115)</b>  <b>: Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	7.20375	Cum
i	Un-Skilled	0.1236	0.8903835	-
3	<p><b>Concrete (AR0303a)</b>  <b>: Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	10.0725	Cum
i	Un-Skilled	3.9	39.28275	-
ii	Skilled	0.18	1.81305	-

4	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	7.7775	Cum
i	Un-Skilled	4.6	35.7765	-
ii	Skilled	0.68	5.2887	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	20.4	Sqm
i	Semi-Skilled	0.05	1.02	-
ii	Skilled	0.05	1.02	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	76.8377985	462	35499.062907
2	Skilled	8.12175	562	4564.4235
3	Semi-Skilled	1.02	512	522.24
<b>Total: 40585.726407</b>				

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>1.72125</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>7.20375</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	7.20375	1 Cum

3	<p><b>Concrete (AR0303a)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>10.0725</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	23.066025	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	4.8348	1 Cum
iii)	<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	9.6696	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	<b>7.7775</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	25.121325	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	3.499875	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	6.99975	1 Cum.
5	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	20.4	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.054468	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.5704	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	7.20375	1 Cum	989.05	7124.8689375
2	<b>BRM340</b>	48.18735	1 Qntl.	561.987	27080.66426445
3	<b>BRM028</b>	8.334675	1 Cum	993.99	8284.58360325
4	<b>BRM045</b>	9.6696	1 Cum.	1545.11	14940.595656
5	<b>BRM056</b>	6.99975	1 Cum.	2154.37	15080.0514075
6	<b>BRM104</b>	0.054468	1Cum.	58573.086	3190.358848248
7	<b>BRM092</b>	2.5704	1Mtr.	229.106	588.8940624
<b>Total: 76290.016779348</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	7.20375	1 Cum	442.25	3185.8584375
2	<b>BRM028</b>	8.334675	1 Cum	442.25	3686.01001875
3	<b>BRM045</b>	9.6696	1 Cum.	1125.5	10883.1348

4	BRM056	6.99975	1 Cum.	1125.5	7878.218625
					<b>Total: 25633.22188125</b>

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 72.1	Rs. 72.1
2	Display Citizen Board @ Rs. 1300	Rs. 1300
3	Any Other Lumpsum @ Rs. 500	Rs. 500
		<b>Total Addition Component Amount (in Rs.): 1872.1</b>

**Total Net Amount (in Rs.): 149999.98552919**