

ESTIMATION DPR

State	Odisha	District	Mayurbhanj	Block	Betnoti	Gram Panchayat	Patalipura
--------------	--------	-----------------	------------	--------------	---------	-----------------------	------------

Work Code	OD/365/3491/120122/390361/00074297 (Construction of CC road from Laxman hansda house to Baidyanath soren House at Sankhirpada)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Betnoti	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	278
Fund Sanction Amount (in Rs.)	500000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	11.9375	240.77592	2874.262545
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	6.7675	1463.584132	9904.80561331

3	<p style="text-align: center;">Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	40.1165	6728.7495628	269933.88183607
4	<p style="text-align: center;">Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	21.41604	8222.0838306	176084.47619948

5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	132.7	216.23489289764	28694.370287517
Total Amount (in Rs.): 487491.79648138					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	11.9375	Cum
i	Un-Skilled	0.516	6.15975	-

2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.7675	Cum
i	Un-Skilled	0.1236	0.836463	-
3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	40.1165	Cum
i	Skilled	0.18	7.22097	-
ii	Un-Skilled	3.9	156.45435	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	21.41604	Cum
i	Un-Skilled	4.6	98.513784	-
ii	Skilled	0.68	14.5629072	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	132.7	Sqm
i	Semi-Skilled	0.05	6.635	-
ii	Skilled	0.05	6.635	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	261.964347	462	121027.528314
2	Skilled	28.4188772	562	15971.4089864
3	Semi-Skilled	6.635	512	3397.12
Total: 140396.0573004				

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.9375	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.7675	Cum
i)	BRM029 : Sand for filling and road blinding	1	6.7675	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	40.1165	Cum
i)	BRM340 : Cement	2.29	91.866785	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	19.25592	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	38.51184	1 Cum.
4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	21.41604	Cum
i)	BRM340 : Cement	3.23	69.1738092	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	9.637218	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	19.274436	1 Cum.
5	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	132.7	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.354309	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	16.7202	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	6.7675	1 Cum	531.74	3598.55045
2	BRM340	161.0405942	1 Qntl.	638.732	102861.78081455
3	BRM028	28.893138	1 Cum	538.16	15549.13114608
4	BRM044	38.51184	1 Cum.	1792.06	69015.5279904
5	BRM056	19.274436	1 Cum.	2193.43	42277.12615548
6	BRM104	0.354309	1Cum.	58573.086	20752.971527574
7	BRM092	16.7202	1Mtr.	229.106	3830.6981412
Total: 257885.78622529					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	6.7675	1 Cum	860.25	5821.741875
2	BRM028	28.893138	1 Cum	860.25	24855.3219645
3	BRM044	38.51184	1 Cum.	681.5	26245.81896

4	BRM056	19.274436	1 Cum.	681.5	13135.528134
					Total: 70058.4109335

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 4874.9179648138
2	Display Citizen Board @ Rs. 5000	Rs. 5000
3	Any Other Lumpsum @ Rs. 2633.2	Rs. 2633.2
		Total Addition Component Amount (in Rs.): 12508.117964814

Total Net Amount (in Rs.): 499999.91444619