

| ESTIMATION DPR | | | | | | | |
|----------------|--------|-----------------|----------|--------------|----------|-----------------------|-----------|
| State | Odisha | District | Rayagada | Block | Muniguda | Gram Panchayat | Patraguda |

| | | | | | | | |
|-------------------------|---|--|--|--|--|--|--|
| Work Code | OD/370/3554/121219/424825/00073608 (CONST OF CC ROAD AT SARABALI SC SAHI) | | | | | | |
| Project Category | Road | | | | | | |

| | | | |
|-----------------------------|---------------------------------|------------------------------|-----------------------------------|
| Financial Year | 2025-26 | Execution Level | PS |
| Executing Agency | Panchayat Samiti, Muniguda | Proposal Date | - |
| Date of Commencement | - | Date of Completion | |
| Scheme Name | Bikashita Gaon Bikashita Odisha | Scheme Component Name | Viksit Gaon Vikshit Odisha (VGVO) |
| Project Sub-Category | CC Road | Project Type | New Work |
| Name of Executant | | | |

Administrative Approval Details

| | |
|---------------------|--|
| Approval No. | |
|---------------------|--|

Technical Sanction Details

| | |
|--------------------------------------|--------|
| Technical Sanction No. | |
| Fund Sanction No. | 5525 |
| Fund Sanction Amount (in Rs.) | 354508 |

ACTIVITY STATEMENT

| S/N | ACTIVITY TAKEN | UNIT | QUANTITY | UNIT PRICE (IN RS.) | TOTAL (IN RS.) |
|-----|----------------|------|----------|---------------------|----------------|
|-----|----------------|------|----------|---------------------|----------------|

| | | | | | |
|---|---|-----|--------|---------------|-----------------|
| 1 | <p align="center">Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p> | Cum | 50.778 | 6812.74280304 | 345937.45405277 |
| Total Amount (in Rs.): 345937.45405277 | | | | | |

LABOUR STATEMENT

| SI.No. | Activity Name | Qty/unit(B=Analysis Basic Qty/HeaderUnit) | Quantity(Meaurement Qty) | Unit |
|--------|--|---|--------------------------|------|
| 1 | <p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p> | - | 50.778 | Cum |

| | | | | |
|----|------------|------|----------|---|
| i | Un-Skilled | 4.6 | 233.5788 | - |
| ii | Skilled | 0.68 | 34.52904 | - |

| Sl.No. | Labour Type | Qty Unit | Rate | Amount |
|----------------------------|-------------|----------|------|-------------|
| 1 | Un-Skilled | 233.5788 | 462 | 107913.4056 |
| 2 | Skilled | 34.52904 | 562 | 19405.32048 |
| Total: 127318.72608 | | | | |

MATERIAL STATEMENT

| Sl.No. | Activity Name/Material | Qty/unit (B=Analysis Basic Qty/Header Unit) | Quantity (Meaurement Qty) | Unit |
|--------|---|---|---------------------------|---------|
| 1 | Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. | - | 50.778 | Cum |
| i) | BRM340 : Cement | 3.23 | 164.01294 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.45 | 22.8501 | 1 Cum |
| iii) | BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken) | 0.9 | 45.7002 | 1 Cum. |

| SI.No. | Material Name | Qty | Unit | Rate | Amount |
|-------------------------------|---------------|-----------|---------|---------|----------------|
| 1 | BRM340 | 164.01294 | 1 Qntl. | 600.692 | 98521.26095448 |
| 2 | BRM028 | 22.8501 | 1 Cum | 483.09 | 11038.654809 |
| 3 | BRM056 | 45.7002 | 1 Cum. | 1737.73 | 79414.608546 |
| Total: 188974.52430948 | | | | | |

ROYALTY STATEMENT

| S/N | Material Name | Qty | Unit | Royalty Rate | Amount |
|---------------------------|---------------|---------|--------|--------------|-------------|
| 1 | BRM028 | 22.8501 | 1 Cum | 91.25 | 2085.071625 |
| 2 | BRM056 | 45.7002 | 1 Cum. | 159.9 | 7307.46198 |
| Total: 9392.533605 | | | | | |

ADDITION COMPONENT

| SI.No. | Item Name | Amount (in Rs.) |
|---|---|-----------------|
| 1 | Provision for Contingency @ Rs. 3570 | Rs. 3570 |
| 2 | Display Citizen Board @ Rs. 5000 | Rs. 5000 |
| Total Addition Component Amount (in Rs.): 8570 | | |

Total Net Amount (in Rs.): 354507.45405277