

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Koraput	<b>Block</b>	Narayan Patana	<b>Gram Panchayat</b>	Narayanapatna

<b>Work Code</b>	OD/363/3477/119895/428609/00072803 (CONSTRUCTION OF CC ROAD AT CHAMPIKOTASAHI NARAYANPATNA)
<b>Project Category</b>	Road

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Narayan Patana	<b>Proposal Date</b>	30-06-2025
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	3655
<b>Fund Sanction Amount (in Rs.)</b>	600000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	48	240.77592	11557.24416
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	43.2	827.294232	35739.1108224

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	46.8	5980.4705598	279886.02219864
4	<p style="text-align: center;"><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	72	217.65463309124	15671.133582569

5	<p align="center"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	32.4	7442.4747286	241136.18120664
<b>Total Amount (in Rs.): 583989.69197025</b>					

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) :</b> Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	48	Cum

	i	Un-Skilled	0.516	24.768	-
2		<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	43.2	Cum
	i	Un-Skilled	0.1236	5.33952	-
3		<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	46.8	Cum
	i	Skilled	0.18	8.424	-
	ii	Un-Skilled	3.9	182.52	-

4	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	72	Sqm
i	Semi-Skilled	0.05	3.6	-
ii	Skilled	0.05	3.6	-
5	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	32.4	Cum
i	Un-Skilled	4.6	149.04	-
ii	Skilled	0.68	22.032	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	361.66752	462	167090.39424
2	Skilled	34.056	562	19139.472
3	Semi-Skilled	3.6	512	1843.2
<b>Total: 188073.06624</b>				

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	48	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	43.2	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	43.2	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	46.8	Cum
i)	<b>BRM340</b> : Cement	2.29	107.172	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	22.464	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	44.928	1 Cum.
4	<p><b>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	72	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.19224	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	9.072	1Mtr.

5	<b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	32.4	Cum
i)	<b>BRM340 : Cement</b>	3.23	104.652	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	14.58	1 Cum
iii)	<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	29.16	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	43.2	1 Cum	673.45	29093.04
2	<b>BRM340</b>	211.824	1 Qntl.	578.232	122483.415168
3	<b>BRM028</b>	37.044	1 Cum	677.37	25092.49428
4	<b>BRM044</b>	44.928	1 Cum.	1857.16	83438.48448
5	<b>BRM104</b>	0.19224	1Cum.	59001.126	11342.37646224
6	<b>BRM092</b>	9.072	1Mtr.	657.146	5961.628512
7	<b>BRM056</b>	29.16	1 Cum.	2258.53	65858.7348
<b>Total: 343270.17370224</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	43.2	1 Cum	88.55	3825.36
2	<b>BRM028</b>	37.044	1 Cum	88.55	3280.2462
3	<b>BRM044</b>	44.928	1 Cum.	331.2	14880.1536

4	BRM056	29.16	1 Cum.	331.2	9657.792
					<b>Total: 31643.5518</b>

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 6000	Rs. 6000
2	Display Citizen Board @ Rs. 5000	Rs. 5000
3	Any Other Lumpsum @ Rs. 5010	Rs. 5010
		<b>Total Addition Component Amount (in Rs.): 16010</b>

**Total Net Amount (in Rs.): 599999.69197025**