

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Kendujhar	<b>Block</b>	Jhumpura	<b>Gram Panchayat</b>	Malda

<b>Work Code</b>	OD/361/3450/119427/385391/00071031 (TOILET REPAIRING, FLOORING & COLORING AT GOVT. PS ANDHARIKHAMAN)						
<b>Project Category</b>	Building						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Jhumpura	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Asset Management School and Mass Education Department	<b>Scheme Component Name</b>	Self/Personal Deposit
<b>Project Sub-Category</b>	Elementary School	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	150000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p><b>Plastering (AR1017) : 20mm thick cement Plaster in CM (1:4) over masonry work in inside.</b> - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	121.48125	272.4286823264	33094.976864864
2	<p><b>miscellaneous (ARM122) : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.</b> - Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.</p>	Sqm	333.61797	5.12	1708.1240064

3	<p style="text-align: center;"><b>Painting (AR0901d) :</b>  <b>Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	333.61797	71.85770801951	23973.022678322
4	<p style="text-align: center;"><b>Painting (AR0918f) :</b>  <b>Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) -</b> Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	Sqm	333.61797	87.9032189	29326.093445884

5	<p><b>Dismantling (AR1612) :</b>  <b>Dismantling and removing 2.5 cm. thick artificial stone flooring -</b>  Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</p>	Sqm	100.068	100.34838709677	10041.6624
6	<p><b>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips -</b>  2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance &amp; royalty of materials as per direction of Engineer-in-charge.</p>	Sqm	100.067	388.4377629248	38869.801622596

7	<p align="center"><b>Painting (AR0903k) :</b>  <b>Painting two coats of enamel paint in inner surface paint (Inner surface)(For repair and maintenance).</b> -  Painting two coats of enamel paint in inner surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)(For repair and maintenance)</p>	Sqm	43.59375	167.03069962581	7281.4945618127
<b>Total Amount (in Rs.): 144295.17557988</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Plastering (AR1017) :</b>  <b>20mm thick cement Plaster in CM (1:4) over masonry work in inside.</b> - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	121.48125	Sqm
	i Un-Skilled	0.24	29.1555	-
	ii Skilled	0.16	19.437	-

2	<b>miscellaneous (ARM122) : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.</b> - Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.	-	333.61797	Sqm
3	<b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)</b> - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	333.61797	Sqm
i	Highly-Skilled	0.053763440860215	17.93645	-
ii	Un-Skilled	0.053763440860215	17.93645	-

4	<p><b>Painting (AR0918f) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) -</b>          Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	333.61797	Sqm
	i Un-Skilled	0.064	21.35155008	-
	ii Highly-Skilled	0.054	18.01537038	-
5	<p><b>Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring -</b> Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</p>	-	100.068	Sqm
	i Un-Skilled	0.21505376344086	21.52	-

6	<b>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance &amp; royalty of materials as per direction of Engineer-in-charge.</b>	-	100.067	Sqm
i	Un-Skilled	0.36	36.02412	-
ii	Highly-Skilled	0.13	13.00871	-
7	<b>Painting (AR0903k) : Painting two coats of enamel paint in inner surface paint (Inner surface)(For repair and maintenance). - Painting two coats of enamel paint in inner surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in- charge.(Inside)(For repair and maintenance)</b>	-	43.59375	Sqm
i	Highly-Skilled	0.13709677419355	5.9765625	-
ii	Un-Skilled	0.12064516129032	5.259375	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	131.24699508	462	60636.11172696
2	Skilled	19.437	562	10923.594

3	Highly-Skilled	54.93709288	612	33621.50084256
				<b>Total: 105181.20656952</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</b>	-	<b>121.48125</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.0744	9.038205	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.021	2.55110625	1 Cum
2	<b>miscellaneous(ARM12 2) :.Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge. - Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.</b>	-	<b>333.61797</b>	Sqm
i)	<b>BRMM122 : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting)</b>	1	333.61797	Sqm

3	<p><b>Painting(AR0901d)</b>  <b>:.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)</b> - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</p>	-	<b>333.61797</b>	Sqm
i)	<p><b>BRM253</b> : Wall cement primer (I.S.I.) Water bound</p>	0.084	28.02390948	1 Ltr
4	<p><b>Painting(AR0918f)</b>  <b>:.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)</b> - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	<b>333.61797</b>	Sqm
i)	<p><b>BRM255</b> : Weather Coat (I.S.I.)</p>	0.125	41.70224625	1 Ltr
5	<p><b>Dismantling (AR1612)</b>  <b>:.Dismantling and removing 2.5 cm. thick artificial stone flooring</b> - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</p>	-	<b>100.068</b>	Sqm

6	<b>Flooring (AR0802ii)</b> :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	<b>100.067</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0858	8.5857486	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.012	1.200804	1 Cum
iii)	<b>BRM057</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	2.301541	1 Cum.
7	<b>Painting(AR0903k)</b> :.Painting two coats of enamel paint in inner surface paint (Inner surface)(For repair and maintenance). - Painting two coats of enamel paint in inner surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)(For repair and maintenance)	-	<b>43.59375</b>	Sqm
i)	<b>BRM141</b> : Enamel paint	0.125	5.44921875	1 Litre

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM340</b>	17.6239536	1 Qntl.	622.032	10962.663105715
2	<b>BRM028</b>	3.75191025	1 Cum	666.51	2500.6857007275
3	<b>BRMM122</b>	333.61797	Sqm	5.12	1708.1240064
4	<b>BRM253</b>	28.02390948	1 Ltr	159.57512	4471.9187181401
5	<b>BRM255</b>	41.70224625	1 Ltr	195.33512	8145.9132755133
6	<b>BRM057</b>	2.301541	1 Cum.	2131.1	4904.8140251

7	BRM141	5.44921875	1 Litre	205.88512	1121.91305625
					<b>Total: 33816.031887846</b>

### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	3.75191025	1 Cum	50.25	188.5334900625
2	BRM057	2.301541	1 Cum.	424.5	977.0041545
					<b>Total: 1165.5376445625</b>

### ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 1442.9517557988
2	Display Citizen Board @ Rs. 1000	Rs. 1000
3	Any Other Lumpsum @ Rs. 3261.8	Rs. 3261.8
		<b>Total Addition Component Amount (in Rs.): 5704.7517557988</b>

**Total Net Amount (in Rs.): 149999.92733568**