

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Koraput	<b>Block</b>	Koraput	<b>Gram Panchayat</b>	Kerenga

<b>Work Code</b>	OD/363/3471/119803/428971/00069423 (Construction of paver block road inside Salmanguda village)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Koraput	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	Pavor Block	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	4027
<b>Fund Sanction Amount (in Rs.)</b>	450000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	9.6	240.77592	2311.448832
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	25.5	1194.227232	30452.794416

3	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	11.04	7469.50517478	82463.337129571
4	<p style="text-align: center;"><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	48	216.70813962884	10401.990702184

5	<p><b>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</b></p>	Sqm	231	642.159	148338.729
---	---	-----	-----	---------	------------

**Total Amount (in Rs.): 273968.30007976**

**LABOUR STATEMENT**

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	9.6	Cum
i	Un-Skilled	0.516	4.9536	-
2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	25.5	Cum
i	Un-Skilled	0.1236	3.1518	-

3	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	11.04	Cum
i	Un-Skilled	4.6	50.784	-
ii	Skilled	0.68	7.5072	-
4	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	48	Sqm
i	Semi-Skilled	0.05	2.4	-
ii	Skilled	0.05	2.4	-

5	<p><b>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</b></p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	231	Sqm
---	--	---	-----	-----

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	58.8894	462	27206.9028
2	Skilled	9.9072	562	5567.8464
3	Semi-Skilled	2.4	512	1228.8
<b>Total: 34003.5492</b>				

#### MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p><b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	9.6	Cum
2	<p><b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	25.5	Cum
i)	<p><b>BRM029 : Sand for filling and road blinding</b></p>	1	25.5	1 Cum
3	<p><b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	11.04	Cum
i)	<p><b>BRM340 : Cement</b></p>	3.23	35.6592	1 Qntl.
ii)	<p><b>BRM028 : Screened and washed sharp sand for mortar</b></p>	0.45	4.968	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	9.936	1 Cum.
4	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	48	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.12816	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.048	1Mtr.

5	miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	231	Sqm
i)	<b>BRM029</b> : Sand for filling and road blinding	0.03	6.93	1 Cum
ii)	<b>BRMM287</b> : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	231	1 Sqm

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	32.43	1 Cum	1081.05	35058.4515
2	<b>BRM340</b>	35.6592	1 Qntl.	588.992	21002.9835264
3	<b>BRM028</b>	4.968	1 Cum	1084.97	5390.13096
4	<b>BRM056</b>	9.936	1 Cum.	2193.43	21793.92048
5	<b>BRM104</b>	0.12816	1Cum.	58715.766	7525.01257056
6	<b>BRM092</b>	6.048	1Mtr.	371.786	2248.561728
7	<b>BRMM287</b>	231	1 Sqm	608.4	140540.4

Total: 233559.46076496

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	32.43	1 Cum	44.25	1435.0275
2	BRM028	4.968	1 Cum	44.25	219.834
3	BRM056	9.936	1 Cum.	206.5	2051.784
					<b>Total: 3706.6455</b>

## ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 3000	Rs. 3000
2	Display Citizen Board @ Rs. 3000	Rs. 3000
3	Any Other Lumpsum @ Rs. 20031	Rs. 20031
		<b>Total Addition Component Amount (in Rs.): 26031</b>

**Total Net Amount (in Rs.): 299999.30007976**