

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Kotpad	Gram Panchayat	Batasona

Work Code	OD/363/3472/119812/428106/00069075 (Construction of paver block road at Patroguda)						
Project Category	Road						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kotpad	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	5436
Fund Sanction Amount (in Rs.)	600000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	17.64	240.77592	4247.2872288
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	64.53	670.693732	43279.86652596

3	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	88.2	216.70813962884	19113.657915264
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	35.28	7199.74947628	254007.16152316

5	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	Sqm	430.2	626.6085	269566.9767
---	---	-----	-------	----------	-------------

Total Amount (in Rs.): 590214.94989318

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	17.64	Cum
i	Un-Skilled	0.516	9.10224	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	64.53	Cum
i	Un-Skilled	0.1236	7.975908	-

3	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	88.2	Sqm
i	Semi-Skilled	0.05	4.41	-
ii	Skilled	0.05	4.41	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	35.28	Cum
i	Un-Skilled	4.6	162.288	-
ii	Skilled	0.68	23.9904	-

5	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	430.2	Sqm
---	--	---	-------	-----

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	179.366148	462	82867.160376
2	Semi-Skilled	4.41	512	2257.92
3	Skilled	28.4004	562	15961.0248
Total:				101086.105176

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	17.64	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	64.53	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	64.53	1 Cum
3	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	88.2	Sqm
i)	<p>BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)</p>	0.00267	0.235494	1Cum.

ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	11.1132	1Mtr.
4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	35.28	Cum
i)	BRM340 : Cement	3.23	113.9544	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	15.876	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	31.752	1 Cum.

5	<p>miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	430.2	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	12.906	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	430.2	1 Sqm

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	77.436	1 Cum	478.15	37026.0234
2	BRM104	0.235494	1Cum.	58715.766	13827.210598404
3	BRM092	11.1132	1Mtr.	371.786	4131.7321752
4	BRM340	113.9544	1 Qntl.	583.047	66440.7710568
5	BRM028	15.876	1 Cum	482.07	7653.34332
6	BRM056	31.752	1 Cum.	2128.33	67578.73416
7	BRMM287	430.2	1 Sqm	608.4	261733.68

Total: 458391.4947104

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	77.436	1 Cum	128.8	9973.7568
2	BRM028	15.876	1 Cum	128.8	2044.8288
3	BRM056	31.752	1 Cum.	255.35	8107.8732
					Total: 20126.4588

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 6000	Rs. 6000
2	Display Citizen Board @ Rs. 3785.05	Rs. 3785.05
		Total Addition Component Amount (in Rs.): 9785.05

Total Net Amount (in Rs.): 599999.99989318