

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Kendrapara	<b>Block</b>	Kendrapada	<b>Gram Panchayat</b>	Chakroda

<b>Work Code</b>	OD/360/3437/119100/396494/00104534 (construction of cc road from ward no 3 prakash chandra house to irrigation canal)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Kendrapada	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/360/3437/119100/396494/00104534/TS
<b>Fund Sanction No.</b>	586
<b>Fund Sanction Amount (in Rs.)</b>	300000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0115a) : Filling foundation and plinth with crusher dust well watered and rammed</b> - Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	20.4	941.505032	19206.7026528
2	<p style="text-align: center;"><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	20.4	6133.08605026	125114.9554253

3	<p align="center"><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	39.44	216.23489289764	8528.3041758829
4	<p align="center"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	18.36	7634.51239362	140169.64754686
<b>Total Amount (in Rs.): 293019.60980085</b>					

**LABOUR STATEMENT**

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0115a) : Filling foundation and plinth with crusher dust well watered and rammed -</b>  Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	20.4	Cum
	i Un-Skilled	0.1236	2.52144	-
2	<p><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	20.4	Cum
	i Skilled	0.18	3.672	-
	ii Un-Skilled	3.9	79.56	-

3	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	39.44	Sqm
i	Semi-Skilled	0.05	1.972	-
ii	Skilled	0.05	1.972	-
4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	18.36	Cum
i	Un-Skilled	4.6	84.456	-
ii	Skilled	0.68	12.4848	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	166.53744	462	76940.29728
2	Skilled	18.1288	562	10188.3856
3	Semi-Skilled	1.972	512	1009.664
<b>Total: 88138.34688</b>				

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0115a) :.Filling foundation and plinth with crusher dust well watered and rammed -</b> Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.4	Cum
i)	<b>BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve</b>	1	20.4	1 Cum
2	<b>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.4	Cum

i)	<b>BRM340</b> : Cement	2.29	46.716	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	9.792	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	19.584	1 Cum.
3	<b>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	<b>39.44</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1053048	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.96944	1Mtr.
4	<b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</b>	-	<b>18.36</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	59.3028	1 Qntl.

ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	8.262	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	16.524	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM026</b>	20.4	1 Cum	688.33	14041.932
2	<b>BRM340</b>	106.0188	1 Qntl.	583.967	61911.4805796
3	<b>BRM028</b>	18.054	1 Cum	647.28	11685.99312
4	<b>BRM044</b>	19.584	1 Cum.	1848.51	36201.21984
5	<b>BRM104</b>	0.1053048	1Cum.	58573.086	6168.0271066128
6	<b>BRM092</b>	4.96944	1Mtr.	229.106	1138.52852064
7	<b>BRM056</b>	16.524	1 Cum.	2294.31	37911.17844
<b>Total: 169058.35960685</b>					

#### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM026</b>	20.4	1 Cum	186.75	3809.7
2	<b>BRM028</b>	18.054	1 Cum	186.75	3371.5845
3	<b>BRM044</b>	19.584	1 Cum.	444.5	8705.088
4	<b>BRM056</b>	16.524	1 Cum.	444.5	7344.918
<b>Total: 23231.2905</b>					

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 3000	Rs. 3000
2	Display Citizen Board @ Rs. 3980	Rs. 3980
<b>Total Addition Component Amount (in Rs.): 6980</b>		

**Total Net Amount (in Rs.): 299999.60980085**