

## Detailed Estimate

**OD/360/3435/119057/396558/00016722 : construction of road from no. 9 A canal to Ananta gopal matha Harijan sahi**  
**Block : Derabish, Panchayat : Chhoti**  
**Created By: ABANI KUMAR MOHANTY**

<b>1. Earth Work (AR0101aa) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift</b>								
Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff wall	2.000	57.000	0.250	0.150	0.000	4.275	-
Total Quantity					4.275 cum (cum)		4.275 Cum (Cubic Meter)	
<b>Amount</b>					<b>4.275 X 175.30368</b>		<b>749.42</b>	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff wall	2.000	57.000	0.250	0.050	0.000	1.425	-
ii	Road	1.000	57.000	2.500	0.100	0.000	14.250	-
Total Quantity					15.675 cum (cum)		15.675 Cum (Cubic Meter)	
<b>Amount</b>					<b>15.675 X 749.275772</b>		<b>11744.90</b>	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff	2.000	57.000	0.250	0.250	0.000	7.125	-
ii	Road	1.000	57.000	2.500	0.100	0.000	14.250	-
Total Quantity					21.375 cum (cum)		21.375 Cum (Cubic Meter)	

<b>Amount</b>						<b>21.375 X 6100.70648248</b>	<b>130402.60</b>	
<b>4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	57.000	3.000	0.100	0.000	17.100	-
Total Quantity					17.1 cum (cum)		17.1 Cum (Cubic Meter)	
<b>Amount</b>						<b>17.1 X 7638.42757176</b>	<b>130617.11</b>	
<b>5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>								
Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff	2.000	57.000	0.000	0.300	0.000	34.200	-
ii	Cutoff	2.000	57.000	0.000	0.100	0.000	11.400	-
Total Quantity					45.6 Sqm (Sqm)		45.6 Sqm (Square Meter)	
<b>Amount</b>						<b>45.6 X 215.22489289764</b>	<b>9814.26</b>	
<b>Total Amount</b>							<b>283328.29</b>	
<b>Addition</b>								
Provision for Contingency (+) @							2833.28	
Display Citizen Board (+) @							2326.00	
Any Other Lumpsum (+) @								
<b>Total Addition</b>							<b>5159.28</b>	
<b>Grand Net Total Amount</b>							<b>288487.57</b>	