

Detailed Estimate

OD/355/3389/118136/397910/00016921 : Const. of CC Road From Maheswar Das to Priyanath Deo House at Pununga
Block : Jagatsinghpur, Gram Panchayat : Punanga
Created By: Sushanta Kumar Sethy

| 1. Earth Work (AR0101aa) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift | | | | | | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|-------|--------|-------|--------------------------------|-------|---------------------------|-----------|
| Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum | | | | | | | | |
| Sl No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | C/W | 2.000 | 34.500 | 0.225 | 0.100 | 0.000 | 1.553 | - |
| Total Quantity | | | | | 1.5525 cum (cum) | | 1.5525 Cum (Cubic Meter) | |
| Amount | | | | | 1.5525 X 179.18208 | | 278.18 | |
| 2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed | | | | | | | | |
| Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | | | | | | | | |
| Sl No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | Road | 1.000 | 34.500 | 2.900 | 0.100 | 0.000 | 10.005 | - |
| Total Quantity | | | | | 10.005 cum (cum) | | 10.005 Cum (Cubic Meter) | |
| Amount | | | | | 10.005 X 506.679832 | | 5069.33 | |
| 3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal | | | | | | | | |
| Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | | | | | | | | |
| Sl No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | C/W | 2.000 | 34.500 | 0.225 | 0.200 | 0.000 | 3.105 | - |
| ii | Road | 1.000 | 34.500 | 3.350 | 0.100 | 0.000 | 11.558 | - |
| Total Quantity | | | | | 14.6625 cum (cum) | | 14.6625 Cum (Cubic Meter) | |
| Amount | | | | | 14.6625 X 6333.02105678 | | 92857.92 | |

4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

| Sl No | Description | No | L | B | D | CF | Quantity | Deduction |
|----------------|-------------|-------|--------|-------|------------------------------------|-------|---------------------------|-----------|
| i | Road | 1.000 | 34.500 | 3.350 | 0.100 | 0.000 | 11.558 | - |
| Total Quantity | | | | | 11.5575 cum (cum) | | 11.5575 Cum (Cubic Meter) | |
| Amount | | | | | 11.5575 X 7883.84818886 | | 91117.58 | |

5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

| Sl No | Description | No | L | B | D | CF | Quantity | Deduction |
|---------------------------------|-------------|-------|--------|-------|-----------------------------------|-------|-------------------------|-----------|
| i | C/W | 2.000 | 34.500 | 0.100 | 0.000 | 2.000 | 13.800 | - |
| ii | Road | 1.000 | 34.500 | 0.200 | 0.000 | 2.000 | 13.800 | - |
| Total Quantity | | | | | 27.6 Sqm (Sqm) | | 27.6 Sqm (Square Meter) | |
| Amount | | | | | 27.6 X 216.23489289764 | | 5968.08 | |
| Total Amount | | | | | | | 195291.09 | |
| Addition | | | | | | | | |
| Provision for Contingency (+) @ | | | | | | | 2000.00 | |
| Display Citizen Board (+) @ | | | | | | | 2708.00 | |
| Any Other Lumpsum (+) @ | | | | | | | | |
| Total Addition | | | | | | | 4708.00 | |
| Grand Net Total Amount | | | | | | | 199999.09 | |