

Detailed Estimate

OD/370/3557/121258/426420/00016591 : Construction of CC road at Nadi Ghat of Halua
Block : Rayagada, Gram Panchayat : Hallua
Created By: RANJIT JENA

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	C/wall	2.000	26.000	0.250	0.250	0.000	3.250	-
Total Quantity					3.25 cum (cum)		3.25 Cum (Cubic Meter)	
Amount					3.25 X 240.77592		782.52	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	C/wall	2.000	26.000	0.250	0.050	0.000	0.650	-
ii	Bed	1.000	26.000	3.150	0.050	0.000	4.095	-
Total Quantity					4.745 cum (cum)		4.745 Cum (Cubic Meter)	
Amount					4.745 X 760.129232		3606.81	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	C/wall	2.000	26.000	0.250	0.200	0.000	2.600	-
ii	Bed	1.000	26.000	3.650	0.100	0.000	9.490	-
Total Quantity					12.09 cum (cum)		12.09 Cum (Cubic Meter)	

Amount						12.09 X 5445.18603704	65832.30	
4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Bed	1.000	26.000	3.650	0.100	0.000	9.490	-
Total Quantity					9.49 cum (cum)		9.49 Cum (Cubic Meter)	
Amount						9.49 X 6993.39074048	66367.28	
5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	C/wall	2.000	26.000	0.000	0.250	0.000	13.000	-
Total Quantity					13 Sqm (Sqm)		13 Sqm (Square Meter)	
Amount						13 X 216.23489289764	2811.05	
Total Amount							139399.97	
Addition								
Provision for Contingency (+) @							1394.00	
Display Citizen Board (+) @							2994.00	
Any Other Lumpsum (+) @								
Total Addition							4388.00	
Grand Net Total Amount							143787.97	