

## Detailed Estimate

**OD/346/3309/116314/393690/00063576 : Repair and restoration of road from CC road to Gopinath Mohapatra house**  
**Block : Soro, Gram Panchayat : Gopinathpur**  
**Created By:Rojalin Jena**

| <b>1. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>   |                  |       |        |        |                                |       |                              |           |
|---|------------------|-------|--------|--------|--------------------------------|-------|------------------------------|-----------|
| Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc   |                  |       |        |        |                                |       |                              |           |
| SI No   | Description      | No    | L      | B      | D                              | CF    | Quantity                     | Deduction |
| i   | SIDE OF CONCRETE | 2.000 | 49.000 | 0.250  | 0.000                          | 0.000 | 24.500                       | -         |
| <b>Total Quantity</b>   |                  |       |        |        | 24.5 Sft (Square Foot)         |       | 2.2761235 Sqm (Square Meter) |           |
| <b>Amount</b>   |                  |       |        |        | 2.2761235 X<br>216.23489289764 |       | 492.18                       |           |
| <b>2. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>  |                  |       |        |        |                                |       |                              |           |
| Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. |                  |       |        |        |                                |       |                              |           |
| SI No   | Description      | No    | L      | B      | D                              | CF    | Quantity                     | Deduction |
| i   | TOP BED          | 1.000 | 49.000 | 10.000 | 0.250                          | 0.000 | 122.500                      | -         |
| <b>Total Quantity</b>   |                  |       |        |        | 122.5 Cft (Cubic Foot)         |       | 3.468808 Cum (Cubic Meter)   |           |
| <b>Amount</b>   |                  |       |        |        | 3.468808 X<br>7372.21052138    |       | 25572.78                     |           |
| <b>Total Amount</b>   |                  |       |        |        |                                |       | <b>26064.96</b>              |           |
| <b>Addition</b>   |                  |       |        |        |                                |       |                              |           |
| Provision for Contingency (+) @   |                  |       |        |        |                                |       | 270.00                       |           |
| Display Citizen Board (+) @   |                  |       |        |        |                                |       | 300.00                       |           |

|  |                 |
|--|-----------------|
| Any Other Lumpsum (+) @                                      | 365.00          |
| Provision for survey investigation and quality control (+) @ |                 |
| <b>Total Addition</b>  | <b>935.00</b>   |
| <b>Grand Net Total Amount</b>                                | <b>26999.96</b> |

**Rojalin Jena**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**